

Tender Inviting Authority: Staff Officer(E&M), BnK Area.								
Name of the Work / Contract No:		Shifting with installation of Weighbridge no. 01 from existing location to Excv. Workshop wrt AKKOCF, B&K Area.						
		Category of Services (To Be Selected by Department)		Category of Bidder / To Be	To Be Entered by Department			
ITC Not Available		Works Contract		Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :				Select	18	0.00	0.00	0.00
PRICE SCHEDULE								
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)								
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE in Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words	
1	2	3	4	5	6	7	8	
1	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	185.31	cum			0.00	INR Zero Only	
2	Supplying and filling in plinth with Jamuna sand under floors including, watering, ramming consolidating and dressing complete.	16.89	cum			0.00	INR Zero Only	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level : 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	14.01	cum			0.00	INR Zero Only	
4	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centering, shuttering, finishing and reinforcement - All work upto plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	32.15	cum			0.00	INR Zero Only	
5	Reinforced cement concrete work in walls (any thickness) including attached plasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	13.98	cum			0.00	INR Zero Only	
6	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	9.63	cum			0.00	INR Zero Only	
7	Providing, hoisting and fixing up to floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centering, shuttering, but excluding cost of reinforcement with 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20mm nominal size).	0.24	cum			0.00	INR Zero Only	
8	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. : Thermo mechanically treated bars	7139.00	Kgs.			0.00	INR Zero Only	
9	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 5.0 in foundation and plinth in : Cement mortar 1:6 (1 cement : 6 coarse sand).	7.34	cum			0.00	INR Zero Only	
10	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns etc. for mass concrete.	44.52	sqm			0.00	INR Zero Only	
11	Centering and shuttering including strutting, propping etc. and removal of form for : Walls (any thickness) including attached plasters buttresses plinth and string courses etc.	134.21	sqm			0.00	INR Zero Only	
12	Centering and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, bressumers and cantilevers.	44.72	sqm			0.00	INR Zero Only	
13	Centering and shuttering including strutting, propping etc. and removal of form for : Columns, Pillars, Piers, abutments, posts & struts.	48.30	sqm			0.00	INR Zero Only	
14	Centering and shuttering including strutting, propping etc. and removal of form for : Suspended floors, roofs, landings, balconies and access platform.	56.21	sqm			0.00	INR Zero Only	
15	Brick work with common burnt clay F.P.S.(non modular) bricks of class designation 5.0 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand).	10.75	cum			0.00	INR Zero Only	
16	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	385.20	Kgs.			0.00	INR Zero Only	
17	6mm cement plaster of mix 1:3 (1 cement : 3 fine sand).	56.21	sqm			0.00	INR Zero Only	
18	12mm cement plaster of mix 1:6 (1 cement : 6 fine sand).	220.92	sqm			0.00	INR Zero Only	
19	Providing and applying plaster of paris putty of 2mm thickness over plastered surface to prepare the surface even and smooth complete.	170.18	sqm			0.00	INR Zero Only	
20	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including priming coat with cement primer.	170.18	sqm			0.00	INR Zero Only	
21	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84kg/10sqm)	106.95	sqm			0.00	INR Zero Only	
22	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	25.62	sqm			0.00	INR Zero Only	
23	Providing and laying polished vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS : 15622 of approved make in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete : Size of tile 600 x 600mm	41.49	sqm			0.00	INR Zero Only	
24	Providing and fixing M.S. round holding down bolts with nuts and washer plates complete.	156.96	Kgs.			0.00	INR Zero Only	
25	Carriage of old weighbridge plate.	1.00	Job.			0.00	INR Zero Only	
26	Providing and fixing 18mm thick gang saw cut mirror polished pre moulded and prepolished) machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size of approved shade, colour and texture laid over 20mm thick base cement mortar 1:4 (1 cement : 4 coarse sand) with joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edge to give high gloss finish etc. complete at all levels : Granite of any colour and shade : Area of slab over 0.50 sqm.	3.78	sqm			0.00	INR Zero Only	
27	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work upto plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20mm nominal size).	18.20	cum			0.00	INR Zero Only	
28	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required	15	point			0.00	INR Zero Only	
29	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of "Single Pole & Neutral" poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.	3	no.			0.00	INR Zero Only	
30	Supplying and fixing metal box of 75x75x60 (nominal size)mm on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc as required.	6	no.			0.00	INR Zero Only	
31	Supplying and fixing metal box of 180x100x60 (nominal size)mm on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc as required.	3	no.			0.00	INR Zero Only	

32	Supplying and fixing metal box of 200x150x60 (nominal size)mm on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc as required.	1	no.			0.00	INR Zero Only
33	Providing and fixing of 32Amp TP&N disconnector fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required.	3	no.			0.00	INR Zero Only
34	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required	12	no.			0.00	INR Zero Only
35	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 amps modular socket outlet and 5/6 amps modular switch, connection etc. as required.	10	no.			0.00	INR Zero Only
36	Supply and drawing of 2 x 4 sq. mm. P.V.C. Insulated Cu Conductor, Single core cable in the existing surface/ recessed steel/ P.V.C. conduit, as required.	50	metre			0.00	INR Zero Only
37	Fitting and fixing of LED light	12	no			0.00	INR Zero Only
38	Supply and drawing of 2 x 1.5 sq. mm. P.V.C. Insulated Cu Conductor, Single core cable in the existing surface/ recessed steel/ P.V.C. conduit, as required.	36	Mtr.			0.00	INR Zero Only
39	Erection of metallic pole(above 08 m and up to 11m) in cement concrete 1:3:6 (1 cement :3 coarse sand :6 graded stone aggregate 40 mm nominal size) foundation including excavation ,refilling etc as required foundation including excavation and refilling etc. as required.	8	Nos			0.00	INR Zero Only
40	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above including binding etc. as required (8 x 4 x 30 x 214=205.44	205.44	kg			0.00	INR Zero Only
41	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per meter) cross arm for 2 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required .	16	set			0.00	INR Zero Only
42	Supplying and erection of 100 mm X 110 mm shackle insulator with G. I. Bolt, nuts and straps etc. as required	12	set			0.00	INR Zero Only
43	Supplying and erection of 100 mm X 80 mm pin insulator complete with G. I. Spindle and nuts etc. as required	24	set			0.00	INR Zero Only
44	Dismantling of pole /strut embedded in cement concrete foundation etc. as required (idle pole/Oh line in mines)	8	nos			0.00	INR Zero Only
45	Dismantling of overhead lines comprising of copper/aluminium overhead conductor, G.I. wire cross arms, insulators etc. as required	321	Kg			0.00	INR Zero Only
46	Supply and erection of stay set complete(galvanized) with 19/20 mm dia x 1.8 mtr long stay rod anchor plate of size 45cm x45cm x7.5 mm thimble stay clamps ,bow tightner7/3.15 stay wire and strain insulator etc in cement concrete1:3:6 (1 cement :3 coarse sand :6 graded stone aggregate 40 mm nominal size) foundation including excavation ,refilling etc as required	3	set			0.00	INR Zero Only
47	Handling of poles on site and transporting of pole form store toworking site.	8	Nos			0.00	INR Zero Only
48	Total impact of GST for the purpose of CTC	1.000	No.		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					