Validate Print Help

4

Quoted Rate in Figures

Quoted Rate in Words

Total in Figures

Percentage BoQ

Tender Inviting Authority: Staff Officer (Civil),CCL, Dhori Area

Name of Work:-Making of pucca drain over Panel-L at 4,5, and 6 incline of Dhori Khas colliery, Dhori Area

Total impact of GST for the purpose of CTC

		Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department					
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)			
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00			
PRICE SCHEDULE								

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
SI. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50 m and lift upto 1.5 m, disposed earth to be levelled and neatly dressed:Ordinary rock	105.00	cum	₹305.67		INR Thirty Two Thousand &Ninety Five and Paise Thirty Five Only
2	12 mm cement plaster of mix :1:4 (1 cement: 4 fine sand)	262.50	sqm	₹231.05	60650.63	INR Sixty Thousand Six Hundred & Fifty and Paise Sixty Two Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size)	50.75	cum	₹6490.90	329413.18	INR Three Lakh Twenty Nine Thousand Four Hundre Thirteen and Paise Seventeen Only

Nos

1.000

Select

0.00 INR Zero Only

0.00 INR Zero Only

422159.15 INR Four Lakh Twenty Two Thousand One Hundred & Fifty Nine and Paise Fifteen Only

0.00

INR Zero Only