

Item Rate BoQ

Tender Inviting Authority: Project Engineer (E&M), Tetariakhar OCP

Name of the Work/ Contract No: Installation of Mesh-Type Lightning Arrestor system at the Checkpost at TTK OCP Under Rajhara Area.

	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #
SL No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P
						TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Providing and fixing of Copper Bonded Lightning Arrestor 1.3 mtr. length, Air Terminal diameter - 16 mm	4	Nos.			0.00 INR Zero Only
2	Erection of RCC/PCC pole of following length in brick ballastandramming the foundation, finishing with 150mm thick cement concrete(1:3:6) layer on top with including excavation and refilling etc as required. Above 11.00 metre and upto 13.00 metre	4	Nos.			0.00 INR Zero Only
3	Erection of angle iron/channel iron cross arm on wood/RCC/PCC/Steel tubular/rail pole etc. as required.	4	Set			0.00 INR Zero Only
4	Supplying and erection of galvanised 'D' iron clamps complete with shackle insulator(75mmX90mm),G.I. bolts, nuts and washers, coach screws etc. as required. (for supporting and clamping the earthing Cable)	8	Set			0.00 INR Zero Only
5	Providing and fixing of 16sqmm copper lug	8	Nos.			0.00 INR Zero Only
6	Providing and fixing of 6 swg , 30 mtr copper wire for sky netting	1	LS			0.00 INR Zero Only
7	Providing and fixing of 16sqmm unarmoured single core copper cable	60	Mtr			0.00 INR Zero Only
8	Safe earthing electrode having two custom made G.I Tube (Galvanised 80 microns minimum) one inside the order of length 2Mtr. (Outer dia 80 mm) field with contuctor crystalline mixture (CCM)	1	Nos.			0.00 INR Zero Only
9	Back fill compound (Bag of 25 kg each)	2	Nos.			0.00 INR Zero Only
10	Supply and fixing charge for item no. 8& 9	1	Nos.			0.00 INR Zero Only
11	Total impact of GST for the purpose of CTC	1	Nos		0.00	0.00 INR Zero Only
Total in Figures						0.00 INR Zero Only
Quoted Rate in Words	INR Zero Only					