

Tender Inviting Authority:	Project Engineer (EnM), PEOCP, Hazaribagh Area					
Name of the Work / Contract No:	Fencing of LT Transformer, providing earthing arrangement as safety point of view for installed at differernt places at Parej East Open Cast Project under Hazaribagh Area.					
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	6	7	8
1	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclose with cover plate having locking arrangement and watering pipe of 2.7 meter long etc with charcoal/ cock and salt as required	12	set			0.00	INR Zero Only
2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	441.66	Kg			0.00	INR Zero Only
3	Providing and laying in position cement concrete 1:3:6 (1cement : 2coarse sand : 6 graded stone aggregate 40 mm nominal size) in foundation of pump, DG set etc including form work etc as required. (2' X 1' X1' = 0.6096 m X 0.3048 m X 0.3048 m = 0.057 Cum x 33 = 1.881 Cum)	1.881	cum			0.00	INR Zero Only
4	Supply & fixing of Barbed wire	50.23	Kg.			0.00	INR Zero Only
5	Supply & fixing of 25 sq mm single core unarmoured Aluminium cable	150	Mtr			0.00	INR Zero Only
6	Supply & fixing of 25 sq mm Aluminium Lug	20	No			0.00	INR Zero Only
7	Dismantling & Installation of 250 KVA, 3.3 KV/440 V Transformer	1	No			0.00	INR Zero Only
8	Painting work	1	No			0.00	INR Zero Only
9	Total impact of GST for the purpose of CTC	1.00	No		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					