

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL						
Name of the Work / Contract No:		Provision of Safety-Related Apparatus at Dakra Main Substation in respect of Dakra Project, NK Area		NIT No. GM (NK)/EnM/eNIT/2025-26/72; dated 16.07.2025.		
		Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract		Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	0.00	0.00	0.00
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Cleaning jungle including uprooting of rank vegetation, grass, brush wood, tress and saplings of girth upto 30 cm measured at a height of 1m above ground level and removal of rubbish upto a distance of 50m outside the periphery of the area cleared.	1820.00	sqm		0.00	INR Zero Only
2	Spray painting of body, radiator, Conservator of 3 MVA Transformer with one coat of primer and two coat of enamel smoke gray paint (01 No. x 1850 Sqft)	1850.00	Sqft		0.00	INR Zero Only
3	Spray painting of body, radiator and Conservator of 1.6 MVA Transformer with one coat of primer and two coat of enamel smoke gray paint (02 Nos. x 1326 Sqft)	2652.00	Sqft		0.00	INR Zero Only
4	Spray painting of body, radiator and Conservator of 1.25 MVA Transformer with one coat of primer and two coat of enamel smoke gray paint (01 No. x 925 Sqft)	925.00	Sqft		0.00	INR Zero Only
5	Spray painting of body, radiator and Conservator of 500 KVA Transformer with one coat of primer and two coat of enamel smoke gray paint (01 No. x 325 Sqft)	325.00	Sqft		0.00	INR Zero Only
6	Spray painting of body, inside and outside of VCB Switch Body with one Coat of Primer and two coat of enamel smoke gray paint (Total nos. of VCB Switches 07 Nos. x 250 sqft approx).	1750.00	Sqft		0.00	INR Zero Only
7	Writing information using radium sticker letters by painting one coat, pasting one layer of radium base and then sticking second layer of sticker letter including borders as per direction of E.I @ VCB Sl. No., Ratio, Power inwards and outwards (B) Transformer rating with Ratio (C) Earthing, displaying boards with Resistance value, Dt. of measurement and measurement value (D) Information template for each pole: Feeder Identification name, Pole No. Four Pole/ TP?DP No. (E) Safety slogan, SOP, COP, Road sign, Electrical sign, Shock Treatment Charts.	190.00	Sqft		0.00	INR Zero Only
8	Providing of galvanized steel/ Fiber Sheet Standard Size	150.00	Sqft		0.00	INR Zero Only
9	Making of Electrical Diagram (Size 5'x 5') as per direction of E.I.	1.00	Nos		0.00	INR Zero Only
10	Providing Gland Bush for armoured cable complete set for connection with VCB switches/ Transformer	8.00	Nos		0.00	INR Zero Only
11	Provision of Fire bucket with sand with stand	2.00	Set		0.00	INR Zero Only
12	Provision of Breather tank with silica gel suitable for 3MVA/1.6 MVA Transformer	2.00	Nos		0.00	INR Zero Only
13	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 50m.	2.27	cum		0.00	INR Zero Only
14	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to Plinth Level 1:4:8 (1 Cement: 4 coarse sand (Zone III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources).	1.77	cum		0.00	INR Zero Only
15	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement: All work up to Plinth Level 1:1.5:3 (1 Cement: 1.5 coarse sand (Zone III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	6.94	cum		0.00	INR Zero Only
16	Plastering with cement mortar (1:3) on brick work in sub-structure as per Technical specifications.	7.53	Sqm		0.00	INR Zero Only
17	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				