

Tender Inviting Authority:	Project Engineer (EnM), PEOCP, Hazaribagh Area					
Name of the Work / Contract No:	Maintenance of 440 v power supply system of Azad nagar colony at parej east open cast project under Hazaribagh Area.					
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By ClL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder In Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Erection of pole of following length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size) foundation including excavation and refilling etc. as required.Above 10.00 metre and upto 12.00 metre	2	No			0.00	INR Zero Only
2	Dismantling of over head lines comprising of copper/ aluminiumover head conductor, G.I. wire, cross arms, insulators etc. as required.	337	Kg			0.00	INR Zero Only
3	Dismantling of pole/ street light standard/ strut embedded incement concrete foundation etc. as required.	1	No			0.00	INR Zero Only
4	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter andabove including binding etc. as required.	337	Kg			0.00	INR Zero Only
5	Supplying and erection of bow stay set complete (galvanised)with 19/20 mm dia X 1.8 metres long stay rod, anchor plate ofsize 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, turn buckle(20 mm X 60 cm), 7/ 4.00 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) foundationincluding excavation and refilling and also with 0.6 m long braceof size 50 mm X 50 mm X 6 mm angle iron with 50 mm dia pulleyfixed at one end of the brace as required.	9	Set			0.00	INR Zero Only
6	Providing and making steel pole collar with cement concrete (1 cement: 3 coarse sand : 6 stone aggregate 20mm) of specified size and shape including form work, plastering if required, curing etc as required. (volume of pole/ pipe not to be deducted)	5.5	CUM			0.00	INR Zero Only
7	lettering of one no. letter in 10 cm height for Marking & numbering of pole (3.7 x10 = 37	198	Letter			0.00	INR Zero Only
8	Erection of cradle guard as required.	12	No			0.00	INR Zero Only
9	making of cradle guard by supplying 6 SWG GI wire	12	No			0.00	INR Zero Only
10	Total impact of GST for the purpose of CTC	1.00	No		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					