

Tender Inviting Authority: Project Engineer (E&M),Religara Project, Agada Area, CCL.						
Name of the Work / Contract No:	Dismantling, erection and commissioning of fixed type-high mast lighting towers along with supply and installation of MCCB in lighting circuit at Religara Project.			NIT No:PE(E&M)/Rel/e-NIT/25-26/12 Dated: 02.08.2025		
Category of Services (To Be Selected by Department)			Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract		Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	0.00	0.00	0.00
<p align="center">PRICE SCHEDULE</p> <p align="center">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</p>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Dismantling, erection and commissioning charges (includes Labour cost, tools and tackles charges only). Crane required during dismantling/Erection or vehicle for transportation will be provided by CCL.	1	job		0.00	INR Zero Only
2	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. (Ordinary Rock) For foundation 2M X 2M X 2M=8 Cum, 2 cum for earthing	10	cum		0.00	INR Zero Only
3	Providing and laying in position cement concrete 1:3:6 (1 cement: 2 coarse sand : 6 graded stone aggregate 20 mm nominal size) in foundation of pump, DG set etc including form work etc as required. 1.5M X 1.5M X2M=4.5 Cum	4.5	cum		0.00	INR Zero Only
4	Supply and fixing of foundation bolts with nuts (Galvanized, size-M24X400mm, 8 nos.) and other nutbolts as required.	45	kg		0.00	INR Zero Only
5	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required	1.00	nos.		0.00	INR Zero Only
6	Supplying and laying 25 mm X 5 mm G.I strip at 0.50 metre below ground as strip earth electrode, including connection/ terminating with G.I. nut, bolt, spring, washer etc. as required. (Jointing shall be done by overlapping and with 2 sets of G.I. nut bolt & spring washer spaced at 50mm)	20	mtr		0.00	INR Zero Only
7	Total impact of GST for the purpose of CTC	1.000	No	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				