

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Project Engineer (E&M), Dhori (K) Colliery

Name of the Work / Contract No:	Providing, fixing and pasting of synthetic insulated electrical mat of 2.5 mm thickness of ISI mark in 11KV substations, Dhori (K) Colliery, Dhori Area				NIT/D(K)/Tender/E&M/25-26/04
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1.01	Supply & providing of synthetic insulated electrical mat 2.5 mm thickness of ISI marked (IS15652 / 2006) in 11 KV grade.	98	M2		0.00	INR Zero Only
1.02	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20mm nominal size stone aggregate.	98	M2		0.00	INR Zero Only
1.03	12mm cement plaster of mix 1:6 & neat cement punning.	98	M		0.00	INR Zero Only
1.04	Labour cost including cleaning dressing and pasting in the floor of 11KV sub-station	1	Job		0.00	INR Zero Only
2	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				