

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: Staff Officer (Civil), Barka-Sayal Area

Name of Work: Repair and maintenance of damaged roof sheets of Haulage room of Banggaha mines, Hatidhari mines, Budh bazar substation Balkudra substation, Riverside filter plant & cheap house substation under Bhurkunda Project, Barka-Sayal Area. (NIT No. 24 of 2025-26)

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		GST Registered Bidder under regular scheme	18.00	102537.69	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
1	2	3.00	4	5	6	7
1	Item Description/ Heading					
1.01	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	3278.96	Kg	77.95	255594.93	INR Two Lakh Fifty Five Thousand Five Hundred & Ninety Four and Paise Ninety Three Only
1.02	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling / self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	494.4	Sqm	571	282302.40	INR Two Lakh Eighty Two Thousand Three Hundred & Two and Paise Forty Only

1.03	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in- charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix).	1.82	Cum	1412.4	2570.57	INR Two Thousand Five Hundred & Seventy and Paise Fifty Seven Only
1.04	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	45.5	Sqm	452.5	20588.75	INR Twenty Thousand Five Hundred & Eighty Eight and Paise Seventy Five Only
1.05	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	34.43	Sqm	32	1101.76	INR One Thousand One Hundred & One and Paise Seventy Six Only
1.06	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	34.43	Sqm	217.7	7495.41	INR Seven Thousand Four Hundred & Ninety Five and Paise Forty One Only
1.07	Total impact of GST for the purpose of CTC	1.00	Nos	102537.69	102537.69	INR One Lakh Two Thousand Five Hundred & Thirty Seven and Paise Sixty Nine Only
Total in Figures					672191.51	INR Six Lakh Seventy Two Thousand One Hundred & Ninety One and Paise Fifty One Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only					