

Validate		Print		Help			
Tender Inviting Authority:		SO(E&M)/ H					
Name of the Work / Contract No:		Repairing of Explosion prevention and fire extinguishing system safety of 3 MVA /11 KV/3.3 Power Transformer make CTR MFG IND PVT LTD, 1 MVA Transformer foundation & Repairing of Oil Soak Tank for 3 MVA Transformer at main substation TNOCP under Hazaribag Area					
Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Supply and fixing of Nitrogen Cylinder, 10 cubic mtr capacity (with Nitrogen)	1	No			0.00	INR Zero Only
2	Supply and fixing of Heat Sensor-Sprinkler (heat sensing part of fire detector)	1	No			0.00	INR Zero Only
3	Supply and fixing of Regulator Assembly	1	No			0.00	INR Zero Only
4	Supply and fixing of Non return Valve (NRV)	1	No			0.00	INR Zero Only
5	Supply and fixing of Indicating Lamp, 220/110VDC Green/Red	4	No			0.00	INR Zero Only
6	Supply and fixing of Pressure Monitor Switch Assembly (PMS)	1	No			0.00	INR Zero Only
7	Supply and fixing of 220/110VDC Hooter (DC Fail)	1	No			0.00	INR Zero Only
8	Supply and fixing of 110V or 220V DC Contactor (2NO+2NC)	1	No			0.00	INR Zero Only
9	Supply and fixing of 110V or 220V DC Push button type lamp	1	No			0.00	INR Zero Only
10	Supply and fixing of Extension Release Switch (Emergency)	1	No			0.00	INR Zero Only
11	Supply and fixing of Auto/manual/off selector switch, 16 Amp	2	No			0.00	INR Zero Only
12	Supply and fixing of TCIV Gasket	1	No			0.00	INR Zero Only
13	Supply and fixing of G02 Limit Switch Assembly	1	No			0.00	INR Zero Only
14	Supply and fixing of Stem actuated valve	1	No			0.00	INR Zero Only
15	Supply and fixing of Cost of Cable 14 CORE 2.5 SQ mm armoured type	70	Mtr			0.00	INR Zero Only
16	Supply and fixing of Cost of Cable 4 CORE 2.5 SQ mm armoured type	70	Mtr			0.00	INR Zero Only
17	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand) For Transformer 3 Mtr X 1 Mtr X 0.24 Mtr X 2 Side=1.44 CUM 2.52 Mtr X 1 Mtr X 0.24 Mtr X 2 Side=1.20 CUM	2.64	CUM			0.00	INR Zero Only
18	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 20 mm nominal size) For Transformer 3 Mtr X 3 Mtr X 0.24 Mtr = 2.16 CUM	2.16	CUM			0.00	INR Zero Only
19	Cement plaster skirting up to 30 cm height, with cement mortar 1:3 (1 cement : 3 coarse sand), finished with a floating coat of neat cement. 18 mm thick	20	SQM			0.00	INR Zero Only
20	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 1.5 m, disposed earth to be levelled and neatly dressed. 2.8.1 Ordinary rock . For Transformer 3 Mtr X 3 Mtr X 1 Mtr = 9 CUM	9	CUM			0.00	INR Zero Only
21	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size) 2.5 Mtr X 2 Mtr X 0.20 Mtr = 0.75 CUM	1	CUM			0.00	INR Zero Only
22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Mild steel and Medium Tensile steel bars	80	Kg			0.00	INR Zero Only
23	Total impact of GST for the purpose of CTC	1.00	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					