Validate	Print Help Item Rate BoQ						
Tender Inviting Authority:	SO(E&M)/ H						
Name of the Work / Contract No:	Comprehensive annual maintenance contract for repair of wiring of Office Building, area for a period of 02 Years	Guest House, C	anteen, Dispensary, Executive I	Hostel, and Officers Club under G	M Unit, Hazaribagh		
	Category of Services (To Be Selected by Department)		Category of Bidder ( To Be Selected by Bidder)	To Be Entered by Department			
ITC Not Available	Works Contract		Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/					,	Rs.)	,, ()
Bidding Firm / Company :			Select	18	0.00	0.00	0.00
п	his BOQ template must not be modified/replaced by the bidder and the same should b	e uploaded aft	PRICE SCHEDULE er filling the relevent columns, o	: else the bidder is liable to be reje	cted for this tender. Bi	dders are allowed to enter the Bi	idder Name and Values only )
NUMBER #	TEXT # Item Description	NUMBER #	TEXT # Units	NUMBER Estimated Rate in	NUMBER # BASIC RATE In	NUMBER #	TEXT #
No.		4		Rs. P	Figures To be entered by the Bidder in Rs. P	Taxes in Rs. P	In Words
1	2	3	4	5	6	7	8
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface /recessed PVC conduit, with piano type switch, phenolic laminated sheet, suitable size MS box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group A	280	Point			0.00	INR Zero Only
2	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm RRLS PVC insulated copper conductor single core cable in surface /recessed PVC conduit, with piano type switch, phenolic laminated sheet, suitable size MS box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group B	449	Point			0.00	INR Zero Only
3	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm RIS PVC insulated copper conductor single core cable in surface /recessed PVC conduit, with piano type switch, phenolic laminated sheet, suitable size MS box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C	82	Point			0.00	INR Zero Only
4	Supplying and fixing PVC batten/ angle holder including connections etc. as required.	95	Each			0.00	INR Zero Only
5	Supplying 12 Module (210mmX135 x 50mm) switch board box	39	Each			0.00	INR Zero Only
6	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required.  15/16 A socket outlet	150	Each			0.00	INR Zero Only
7	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required.  15/16 A switch	150	Each			0.00	INR Zero Only
8	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required. 5/6 A socket outlet	206	Each			0.00	INR Zero Only
9	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required. 5/6  A switch	206	Each			0.00	INR Zero Only
10	Supplying and fixing two module stepped type electronic fan regulatoron the existing modular plate switch box including connections but excluding modular plate etc. as required.	23	Each			0.00	INR Zero Only
11	Supplying and fixing 20 A, 240 V, SPN Industrial type socket outlet, with 2 pole and earth, metal enclosed plug top alongwith 20 A "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning et as: a required.	39	Each			0.00	INR Zero Only
12	Supplying and fixing 3 pin, 5 A ceiling rose on the existing junction box/ wooden block including connections etc. as required.	170	Each			0.00	INR Zero Only
13	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 6 way, Double door	40	Each			0.00	INR Zero Only
14	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB D8 complete with connections, testing and commissioning etc. as required. Single pole and neutral	133	Each			0.00	INR Zero Only
15	Supplying, installing, testing and commissioning of following capacity End Feed Unit made of 1.6mm thick sheet steel enclosure duly painted with powder coating to existing rising mains complete with TPN disconnector FSU and HRC fuses, mounting stands, cable end box, brass compression gland, connections, earthing etc. as required.200A	6	Each			0.00	INR Zero Only
16	Supplying, installing, testing and commissioning of following capacity End Feed Unit made of 1.6mm thick sheet steel enclosure duly painted with powder coating to existing rising mains complete with TPN disconnector FSU and HRC fuses, mounting stands, cable end box, brass compression gland, connections, earthing etc. as required.400A	1	Each			0.00	INR Zero Only
17	Supply and Fixing of 32A Switch Fuse Unit SPN	38	Each			0.00	INR Zero Only
18	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 2 X	270	Metre			0.00	INR Zero Only
19	1.5 sq. mm + 1 X 1.5 sq. mm earth wire Wiring for circuit/ submain wiring alongwith earth wire with the following 3zes of FRLS PVC Insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	2066	Metre			0.00	INR Zero Only
20	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 2 X	454	Metre			0.00	INR Zero Only
21	4 sq. mm + 1 X 4 sq. mm earth wire  Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 2 X	540	Metre			0.00	INR Zero Only
22	6 sq. mm + 1 X 6 sq. mm earth wire  Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcos1/coke and salt as required.	26	Each			0.00	INR Zero Only
23	Providing and fixing 4.00 mm dia copper wire on surface or in recess for loop earthing as required.	520	Metre			0.00	INR Zero Only
24	Total impact of GST for the purpose of CTC	1.00	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Word	ds				INR Zero Only		