

| | | | | | | |
|--|--|---|-----------------------------|-------------------|-----------------------------------|---|
| Tender Inviting Authority: | PE EnM, TSOCP | | | | | |
| Name of the Work / Contract No: | Erection/maintenance of pipeline for water arrangement to crusher and making of water filling point at different locations of TSOCP under Hazaribagh Area. | | | | | |
| . | Category of Services (To Be Selected by Department) | Category of Bidder (To Be Selected by Bidder) | To Be Entered by Department | | | |
| ITC Available | Works Contract | Bidder's Status (Mandatory) | Rate of GST (in %) | Total GST(in Rs.) | GST to be Paid By Bidder (in Rs.) | GST to be Paid By CIL/Subsidiary (in Rs.) |
| Name of the Bidder/ Bidding Firm / Company : | | Select | 18 | 0.00 | 0.00 | 0.00 |

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

| NUMBER # | TEXT # | NUMBER # | TEXT # | NUMBER | NUMBER # | NUMBER # | TEXT # |
|----------------------|---|---------------|--------|-------------------------|--|-------------------------------------|-----------------------|
| Sl. No. | Item Description | Quantity | Units | Estimated Rate in Rs. P | BASIC RATE In Figures To be entered by the Bidder in Rs. P | TOTAL AMOUNT Without Taxes in Rs. P | TOTAL AMOUNT In Words |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| 1 | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 40 mm nominal dia Pipes | 250.00 | m | | | 0.00 | INR Zero Only |
| 2 | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 25 mm nominal dia Pipes | 150.00 | m | | | 0.00 | INR Zero Only |
| 3 | Making and Fixing of short pieces 6" dia | 2.00 | no. | | | 0.00 | INR Zero Only |
| 4 | Supply and fixing of 4inch Flenge | 8.00 | Nos. | | | 0.00 | INR Zero Only |
| 5 | Making of water filling point | 3.00 | Nos. | | | 0.00 | INR Zero Only |
| 6 | Supply and fixing of 1hp, Tubewell pump | 1.00 | No. | | | 0.00 | INR Zero Only |
| 7 | Supply of Helical pipe 4 inch | 25.00 | Feet | | | 0.00 | INR Zero Only |
| 8 | Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. Internal work - 50 mm dia nominal bore | 25.00 | Mtr | | | 0.00 | INR Zero Only |
| 9 | Supply of 4" dia Sluice Valve C.I., ISI Mark | 2.00 | no. | | | 0.00 | INR Zero Only |
| 10 | Making and Fixing of short piece 4"G.I. | 4.00 | no. | | | 0.00 | INR Zero Only |
| 11 | Stacking of 6 inch pipe | 2.00 | Day | | | 0.00 | INR Zero Only |
| 12 | Steel box 5X10X18 inch | 5.00 | Nos. | | | 0.00 | INR Zero Only |
| 13 | Shifting of boom barrier | 1.00 | No | | | 0.00 | INR Zero Only |
| 14 | Repairing of transformer shed | 1.00 | No | | | 0.00 | INR Zero Only |
| 15 | Total impact of GST for the purpose of CTC | 1.00 | Nos | | 0.00 | 0.00 | INR Zero Only |
| Total in Figures | | | | | | 0.00 | INR Zero Only |
| Quoted Rate in Words | | INR Zero Only | | | | | |