

Name of the Work - Providing and replacement of automatic star-delta starters and cables for different mono block pumps at filter plant and submersible flat cable and Direct On Line starter for different submersible pumps installed at different sites " under Township of Rajrappa Area

ITC Not Available

| SI .No | Description | Quantity | Units | Rate |
|--------|--|----------|-------|------|
| 1 | Supply of ISI Marked Automatic Star-Delta Starters confirming to IS: 13947-4 with suitable over load relay range and contactor size & timer 415 V, 3-Phase with two earthing terminals (10 hp) | 6 | each | |
| 2 | Supply of ISI Marked Direct On-Line Starters confirming to IS: 13947-4 with suitable over load relay range and contactor size, 415 V, 3-Phase with two earthing terminals (10 hp) | 6 | each | |
| 3 | Supplying and laying of submersible flat cable ISI marked 3 core copper wire of suitable size with proper clamping of approved make. (4 sqmm) | 300 | mtr | |
| 4 | Supply of XLPE insulated FRLS heavy duty power cable conforming IS-7098 (Part-1) 1988, 1100 Volt grade, 3 core ISI marked with copper stranded/solid conductor.(4 sqmm) | 130 | mtr | |
| 5 | Supplying & fixing pin terminal lugs as per ISS specification suitable for cable evenly cramped with high pressure tool & connection to switch gear terminal as required complete. Copper Lugs Tube type (upto 16 sqmm conductor size) | 100 | each | |
| 6 | Installation of 10 hp Automatic star-Delta starter with connection and supporting of armoured power cable 3 core 4 sqmm and testing of pump | 6 | each | |
| 7 | Installation of 10 hp Direct-on-line starter with connection and proper laying of submersible flat cable 3 core 4 sqmm | 6 | each | |
| 8 | Total impact of gst | 1 | no | |
| 9 | Total | 1 | no | |