

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL

Name of the Work / Contract No:	Installation of two (02 nos.) bus bar inside metal box with isolator and DTH, MCCB Switch of rating 800 A and 630 A for the transformer of 630 kVA (11 kV/440V) in A type and B type Colony under Dakra Project, NK Area	NIT No. GM (NK)/EnM/eNIT/2025-26/83; dated 22.08.2025.			
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Metallic Bus Bar Box 1.5 x 0.65 x 0.6 M including fabrication work with angle, channel and iron sheet etc.	1.00	Nos		0.00	INR Zero Only
2	Metallic Bus Bar Box 1.1 x 0.65 x 0.6 M including fabrication work with angle, channel and iron sheet etc.	1.00	Nos		0.00	INR Zero Only
3	5 x 50 mm copper strip	16.39	kg		0.00	INR Zero Only
4	Bus bar insulator 440 V, 6" length	16.00	Nos		0.00	INR Zero Only
5	Copper lugs 70 Sq mm	76.00	Nos		0.00	INR Zero Only
6	Bus gland double comprasion brass gland bush size suitable for 70 sq mm cable.	7.00	Nos		0.00	INR Zero Only

7	Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required. 800 A, 50 KA, TPMCCB	3.00	Nos		0.00	INR Zero Only
8	Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required. 630 A, 50 KA, TPMCCB	2.00	Nos		0.00	INR Zero Only
9	Earthing with G.I. earth plate 600 mm X 600mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/coke and salt as required.	2.00	Nos		0.00	INR Zero Only
10	Providing and fixing 25mm X 5mm G.I. strip on surface or in recess for connections etc. as required.	20.00	Mtr		0.00	INR Zero Only
11	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				