

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority:	Project Engineer (EnM), JOCP, Hazaribagh Area					
Name of the Work / Contract No:	Reorganization of 3.3KV HT both overhead feeders near EKO shovels to supply one shovel from the 1.6 MVA feeder for load optimization, along with erection of two OH line spans near the eastern sump to power a 2000 GPM pump-motor set and dismantling of 5 poles under Jharkhand OCP, Hazaribagh Area.					
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (In %)	Total GST(In Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Erection of metallic pole of above 10.00 metre and up to 12.00 metre in cement concrete 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 40mm nominal size) foundation including excavation and refilling etc. as required.	11	Nos			0.00	INR Zero Only
2	Providing and making steel pole collar with cement concrete (1cement : 3 coarse sand : 6 stone aggregate 20mm) of specified size and shape including form work, plastering if required, curing etc as required. (volume of pole/ pipe not to be deducted)	2.21	cum			0.00	INR Zero Only
3	Supplying of two lengths of channel iron /50mmx40mmx6mm (7.14Kg per meter) double pole cross arm for three wire 11KV O/H line conductors complete with through bolts and nuts for clamping to the poles. 50mmx6mm MS flats welded on one side to the channel iron and with bolts and nuts on the other side for tying the cross arms together, including drilling holes for insulator pins/fittings, bolts, nuts and washers etc. (as per drawing) and painting with primer and finish paint as required.	7	Set			0.00	INR Zero Only
4	Supplying of 50 mm X 8 mm M.S. flat iron pole top bracket/ cross arm for single 11/22/33 KV over head line conductor complete with fixing clamps, bolts, nuts and washers including drilling holes for insulator pins, bolts and nuts etc and painting with primer and finish paint as required.	5	Nos			0.00	INR Zero Only
5	Erection of pole top/ straight two wire/ V shape two wire, angle iron/ channel iron, cross arm on steel tubular /rail/PCC pole for 11/22/33 Kv as required.	12	Set			0.00	INR Zero Only
6	Supply & erection of galvanised stay sets for 11 KV over head lines complete with 19/20mm diax1.8m long stay rod, anchor plate of size 5cmx15cmx7.5mm, thimble, stay clamps, turn buckle (20 mm x 600 mm), 7/4.00 mm dia 0.1 stay wire and 11 KV strain insulator etc. in cement concrete 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 40mm nominal size) foundation including excavation and refilling etc. as required.	13	Set			0.00	INR Zero Only
7	Erection of all aluminium conductor of 7/3.40 mm to 7/4.00 mm diameter and above including binding etc. as required.	225.23	Kg			0.00	INR Zero Only
8	Supplying and erection of 11KV pin insulator complete with large steel head GI pin, nuts, washers etc.as required.	15	Set			0.00	INR Zero Only
9	Supplying and erection of 11Kv disc insulator for 11Kv over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required.	18	Set			0.00	INR Zero Only
10	Erection of cradle guard as required	3	each			0.00	INR Zero Only
11	Making of cradle guard as required	69.17	Kg			0.00	INR Zero Only
12	Supply of 8SWG GI Wire cradling of O/H cross line	69.17	Kg			0.00	INR Zero Only
13	Dismantling of pole/ street light standard/ strut embedded in cement concrete foundation etc. as required.	5	Nos			0.00	INR Zero Only
14	Dismantling of O.H line comprising of copper/aluminium O.H conductor GI wire, cross arms, insulators etc. as required.	338.53	Kg			0.00	INR Zero Only
15	Supply and fixing of 3.3KV 630A gang operated switch (vertical type)	2	nos			0.00	INR Zero Only
16	Supply & Fixing of five spikes lightning conductor of required size. 30 inch X 25mm X 50mm	2	nos			0.00	INR Zero Only
17	Supply & Fixing of Support Insulator 90mm X 30mm 11KV /3.3KV grade	2	nos			0.00	INR Zero Only
18	Earthing with copper earth plate 600 mm X 600 mm X 3mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required	2	no			0.00	INR Zero Only
19	Supply & Fixing of copper cable single core flexible type 1100 voltage grade 10 sqmm	26	mtr			0.00	INR Zero Only
20	Total impact of GST for the purpose of CTC	1.00	No		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						