

Tender Inviting Authority: Staff officer(E&M), Dhori Area.

Name of the Work / Contract No:	Breakdown maintenance of LT line of different locations at mine area under SDOCM ,Dhori area.							
.	Category of Services (To Be Selected by Department)		Category of Bidder (To Be	To Be Entered by Department				
ITC Available	Works Contract		Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :			Select	18	0.00	0.00	0.00	

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Disconnection and re-connection of conductor jumper and OH line during Breakdown rectification for power supply HEMM, pumps and lighting transformers etc installed at the mine area of SDOCM, Dhori area.	480	Nos			0.00	INR Zero Only
2	Dismantalling of L.T cable upto size 35 sqmm for fault rectification	1100	Mtr			0.00	INR Zero Only
3	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct asrequired.(Upto 35 sq. mm)	1100	Mtr			0.00	INR Zero Only
4	Relocation/dismantle and re-erection after departmental maintenance of light fitting of 150W/300/500W installed at the different location of SDOCM mine area, Dhori Area.	1385	Nos			0.00	INR Zero Only
5	Repairing of stay/cradle guard/earth wire etc LT- 200 set	200	Set			0.00	INR Zero Only
6	Re-erection/tensioning of the conductor due to damage/HT OH line & 440/220v	1250	Kg			0.00	INR Zero Only
7	Cleaning jungle including uprooting of rank vegetation grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 outside the periphery of the area cleared.	2000	Sqm			0.00	INR Zero Only
8	Erection of LT pin/Disc insulator for replacement of faulty insulator	250	Nos			0.00	INR Zero Only
9	Cleaning of corbon from service wire for light by using equipment	850	Nos			0.00	INR Zero Only
10	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					

Tender Inviting Authority: Staff officer(E&M), Dhori Area.								
Name of the Work / Contract No:	Diverson of 3.3 kv oh line feeder no-01 for railwayline side to left side of KPS transporting road to Tarmi siding in r/o SDOCM.							
.	Category of Services (To Be Selected by Department)		Category of Bidder (To Be	To Be Entered by Department				
ITC Available	Works Contract			Bidder's Status (Mandato ry)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :				Select	18	0.00	0.00	0.00
PRICE SCHEDULE								
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)								
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #	
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words	
1	2	3	4	5	6	7	8	
1	Erection of steel tublor pole of length exceeding 10 mtrs but not exceeding 12 mtr in cement concrete 1:3:6 (1 cement :3 coarse sand :6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc as required (pole supply by department).	21	Nos			0.00	INR Zero Only	
2	Erection of all aluminium conductor of 7/1.96 mm to 7/3.10 mm diameter including binding etc. asrequired.	564.96	kg			0.00	INR Zero Only	
3	Supplyinganderectionofgalvanisedstaysetfor11KVoverhead lines complete with 19/ 20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm thick, thimble, stay clamps,turnbuckle(20mmX600mm),7/3.15mmdiaG.I.stay wire and 11 KV strain insulator etc in cement concrete 1:3:6 (1 cement: 3coarse sand: 6grade d stone aggregate 40mmnominal size) foundation including excavation and refilling etc.as required.	16	Nos			0.00	INR Zero Only	
4	Supplying and erection of 11 KV disc insulator for 11 KV over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required.	72	Nos			0.00	INR Zero Only	
5	Supplying and erection of 11 KV pin insulator complete with large steel head G.I.pin ,nuts, washers etc as required.	45	Nos			0.00	INR Zero Only	
6	Supply and erection of 8 SWG GI wire for earth continuity& cradling.	184.44	kg			0.00	INR Zero Only	
7	Erection of earth continuity.	72.05	kg			0.00	INR Zero Only	
8	Ercetion of cradle wire.	264	Nos			0.00	INR Zero Only	
9	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 2 wireover head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required .	27	Nos			0.00	INR Zero Only	
10	Erection of pole top/straight two wire/Vshape two wire,angle iron/ channel iron, cross arm on steel tubular/ rail/ PCC pole for 11/22/ 33 KV as required.	27	Nos			0.00	INR Zero Only	
11	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for two 11 KV over head line conductors complete with 50mmX50mmX6mm (angle iron bracket welded to the channel iron and complete with 50mmX6mmM.S.flatiron clamps, bolts and nuts including drilling holes for insulator pins, bolts, nuts and washers etc (as per drawing) and painting with primer and finish paint asrequired.	21	Nos			0.00	INR Zero Only	
12	Erection of double pole 3 wire cross arm for 11KV over head lines asrequired	21	Nos			0.00	INR Zero Only	
13	Dismantling of pole/ street light standard/ strut embedded in cement concrete foundation etc. asrequired.	21	Nos			0.00	INR Zero Only	
14	Transporting of pole from dismantle place to proposed place.	21	Nos			0.00	INR Zero Only	
15	Dismantling of over head lines comprising of copper/ aluminiumover head conductor, G.I. wire, cross arms, insulators etc. as required.	1586.67	kg			0.00	INR Zero Only	
17	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only	
Total in Figures						0.00	INR Zero Only	
Quoted Rate in Words		INR Zero Only						

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Staff officer(E&M), Dhori Area.

Name of the Work / Contract No:	Laying of 06" pipe line from 3p pump to dishcharge point near KPS road tanker point in r/o SDOCM project.						
.	Category of Services (To Be Selected by Department)		Category of Bidder (To Be	To Be Entered by Department			
ITC Available	Works Contract		Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This B00 template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Laying of 6" dia pipe .	690	Mtr			0.00	INR Zero Only
2	Providing of 6" dia bend as per required.	6	Nos			0.00	INR Zero Only
3	Providing of 6" dia GI flange as per required.	256	Pcs			0.00	INR Zero Only
4	Fitting & fixing of 6" dia bend.	6	Nos			0.00	INR Zero Only
5	Fitting & fixing of 6" dia jointer/nipple.	5	Nos			0.00	INR Zero Only
6	Providing of C.I.sluiice valve (with caps) class II : 150 mm dia.	1	Nos			0.00	INR Zero Only
7	Providing of C.I.N R V (with caps) class II : 150 mm dia.	1	Nos			0.00	INR Zero Only
8	Fitting & fixing of 6" dia footvalve.	1	No			0.00	INR Zero Only
9	Fitting & fixing of 6" dia Non return valve.	1	No			0.00	INR Zero Only
10	Providing of MS Nut bolt with washer .	260	Mtr			0.00	INR Zero Only
11	Providing & fixing of rubber packing as per required.	135	nos			0.00	INR Zero Only
12	Loading/unloading of 6" dia pipe from KP E&M workshop to propose working place	115	Mtr			0.00	INR Zero Only
13	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.Ordinary rock	200	cum			0.00	INR Zero Only
14	Cutting work :-	4823.04	inch			0.00	INR Zero Only
15	Welding work :-	9646.08	inch			0.00	INR Zero Only
17	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					

<div> <div>Validate</div> <div>Print</div> <div>Help</div> </div>		Item Rate BoQ					
Tender Inviting Authority: Staff officer(E&M), Dhori Area.							
Name of the Work / Contract No:		*Fresh wiring in officer's club under G.M. unit, Dhori					
Category of Services (To Be Selected by Department)			Category of Bidder (To Be)	To Be Entered by Department			
ITC Not Available		Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C - a) - Bulb point	95	points			0.00	INR Zero Only
2	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C - b) - Tube point	112	points			0.00	INR Zero Only
3	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C - c) - Fan point	26	points			0.00	INR Zero Only
4	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C - d) - Exhaust fan point	10	points			0.00	INR Zero Only
5	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C - e) - Call bell point	3	Points			0.00	INR Zero Only
6	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 amps modular socket outlet and 5/6 amps modular switch connection etc. as required. (for light chum ton be used in non residential buildings)	88	Each			0.00	INR Zero Only
7	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch connection etc. as required.	35	Each			0.00	INR Zero Only
8	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/isolator). : 6 way, double door. (for A.C. & other equipments)	20	Each			0.00	INR Zero Only
9	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole & neutral.	40	Each			0.00	INR Zero Only
10	Supplying and fixing stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate as required.	26	Each			0.00	INR Zero Only
11	Providing and fixing following capacity TPN&N disconnector fuse switch unit inside the existing panel board with ISI marked HBC fuses including drilling holes in cubicle panel, making connections, etc. as required. : 100 Amp.	2	Each			0.00	INR Zero Only
12	Supplying and drawing following sizes FRLS PVC insulated copper conductor, single core cable in existing surface/ recessed steel/ PVC conduit as required. : 3 x 4 sq.mm	780	Mtrs.			0.00	INR Zero Only
13	Supplying and drawing following sizes FRLS PVC insulated copper conductor, single core cable in existing surface/ recessed steel/ PVC conduit as required. : 3 x 1.5 sq.mm	850	Mtrs.			0.00	INR Zero Only
14	Supplying and fixing 3 pin, 5 amps ceiling rose on the existing junction box/ wooden block including connection etc. as required.	148	Each			0.00	INR Zero Only
15	Supplying and fixing brass batten/ angle holder including connection etc. as required.	95	Each			0.00	INR Zero Only
16	Earthing with copper earth plate 600 mm x 600 mm x 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	4	Each			0.00	INR Zero Only
17	Supplying, installing, testing and commissioning of following capacity TPN distribution tap off box made of 1.6 mm thick sheet steel enclosure duly painted with powder coating on existing rising mains complete with HBC fuses, interconnections, earthing etc. as required. : 63 amps TPN, 8 way.	2	Each			0.00	INR Zero Only
18	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FLRS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. : 4 x 16 sqmm + 2 x 6 sqmm earth wire.	220	Mtrs.			0.00	INR Zero Only
19	-do- 2 x 6 sqmm + 1 x 6sqmm earth wire.	180	Mtrs.			0.00	INR Zero Only
20	-do- 4 x 25 sqmm for main power connection.	280	Mtrs.			0.00	INR Zero Only
21	Supply of LED bulb 12 watt.	60	Each			0.00	INR Zero Only
22	Providing and fixing 25 mm x 5 mm dia G.I. strip on surface or in recess for connections etc. as required.	80	Mtrs.			0.00	INR Zero Only
23	Supply and fixing of Smart LED 20 watt round wiff.	65	Each			0.00	INR Zero Only
24	Supply and fixing of Exhaust fan.	4	Each			0.00	INR Zero Only
25	Supply and fixing of changeover switch.	2	Each			0.00	INR Zero Only
26	Supply and fixing of A.C. box	10	Each			0.00	INR Zero Only
27	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					

Tender Inviting Authority: Staff officer(E&M), Dhori Area.

Name of the Work / Contract No:

Fiber connectivity of all CCTV NVR sites with core intranet switches installed in different areas in rental basis for 1 year with repairing and reconditioning of CCTV and CAMC for 1 year with supply and repairing of anticipatory spares in Dhori Area.”

Category of Services (To Be Selected by Department)

Category of Bidder (To Be)

To Be Entered by Department

ITC Available

Works Contract

Bidder's Status (Mandatory)

Rate of GST (in %)

Total GST(in Rs.)

GST to be Paid By Bidder (in Rs.)

GST to be Paid By CIL/Subsidiary (in Rs.)

Name of the Bidder/ Bidding Firm / Company :

Select

18

0.00

0.00

0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Repairing, Reconditioning, Supply & Installation of 64 Channel NVR	2	Nos			0.00	INR Zero Only
2	upply & Installation of Workstation	4	Nos			0.00	INR Zero Only
3	Supply & Fixing of 8 Terabyte Surveillance Hard Disk Drive for NVR	6	Nos			0.00	INR Zero Only
4	Repairing, Reconditioning, Supply of 8 Channel NVR	12	Nos			0.00	INR Zero Only
5	Repairing, Reconditioning, Supply of Bullet Camera	20	Nos			0.00	INR Zero Only
6	Repairing, Reconditioning, Supply of Layer 2 Plus Managed Switch (8 Port with 2 SFP Port)	10	Nos			0.00	INR Zero Only
7	Repairing, Reconditioning, Supply of Layer 2 Plus Managed Switch (24 Port with 4 SFP Port)	4	Nos			0.00	INR Zero Only
8	Supply of 1 KVA Sine Wave Inverter with 150 Ah Battery and Stand	7	Nos			0.00	INR Zero Only
9	Supply of 1 KVA Online UPS with 26 Ah Battery and Stand	3	Nos			0.00	INR Zero Only
10	Replacement of CAT-6 Cable (305 Meter = 1 Box)	4	Nos			0.00	INR Zero Only
11	Replacement of Giga SM 20 Km Media Convertor in Pair	12	Nos			0.00	INR Zero Only
12	Supply of Giga SM/LC 20 Km SFP Module in Pair	12	Nos			0.00	INR Zero Only
13	Fiber Connectivity of All CCTV NVR Sites with Core Intranet Switches Installed in Different Areas in Rental Basis for Twelve Months	12	Nos			0.00	INR Zero Only
14	Centralised View in Respective Project Officer & General Manager Office with Respective Areas	4	Nos			0.00	INR Zero Only
17	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					

Tender Inviting Authority: Staff officer(E&M), Dhori Area.									
Name of the Work / Contract No:				REPAIRING AND MAINTENANCE OF 02 NOS 3.3 KV HT MOTOR AND 01 NOS 440V LT MOTORS INSTALLED AT AADOCM UNDER DHORI AREA.					
Category of Services (To Be Selected by Department)				Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Available				Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :				Select	18	0.00	0.00	0.00	0.00
PRICE SCHEDULE									
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #		
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words		
1	2	3	4	5	6	7	8		
1	PART-A-REPAIRING OF 324KW/435 HP ,3.3KV 1490 RPM GEC MAKE INDUCTION MOTOR ATTACHED WITH 2000 GPM PUMP UNDER AADOCM DHORI AREA.	1	nos			0.00	INR Zero Only		
2	Cooling fan new making as per sample with casting, machining, drilling, tapping, new hub making and tightening with key ways, cutting alignment and balancing on lathe machine with material.	1	NOS			0.00	INR Zero Only		
3	Rotor and rotor shaft alignment checking on lathe machine and rectification and its alignment setting by cut machining and polishing by stone file and complete balance checking.	1	JOB			0.00	INR Zero Only		
4	End cover housing repairing by CI electrode welding and machining as per bearing size.	2	JOB			0.00	INR Zero Only		
5	Gas heating and cutting grinding etc. work of both end connection points strip bars for old damage bar dismantling from rotor.	60	NOS			0.00	INR Zero Only		
6	Rotor shaft bearing housing repairing electrode welding on bearing fitting place or sleeve making as per bearing size.	2	JOB			0.00	INR Zero Only		
7	Complete motor set dismantling, after repairing work its complete assembling/commissioning with testing, cheking charge	1	JOB			0.00	INR Zero Only		
8	Repairing and setting of terminal box and new making of its cover by iron sheet.	2	NOS			0.00	INR Zero Only		
9	Complete motor coil cleaning ,after cleaning its varnishing/heating,tapping etc.	1	JOB			0.00	INR Zero Only		
10	After repairing and changing of strip bars complete new brazing of both end points by gas heating ,silver rod brazing and copper bars shape making of rotor strip bars after this bars fixing in same slots.	60	NOS			0.00	INR Zero Only		
11	Damage bearing of drive and non drive end removing by puller and gas heating and then new bearing fitting.	2	JOB			0.00	INR Zero Only		
12	Providing and fixing of drive END BEARING NO. NU321 ECJ/C3	1	NOS			0.00	INR Zero Only		
13	Providing and fixing of drive NON-END BEARING NO. 6321 -C3	1	NOS			0.00	INR Zero Only		
14	Coil moulding charges	60	nos			0.00	INR Zero Only		
15	PART-B-REPAIRING OF 168KW/225 HP ,3.3KV 1485 RPM GEC MAKE INDUCTION MOTOR ATTACHED WITH 1000 GPM PUMP UNDER AADOCM DHORI AREA.	1	nos			0.00	INR Zero Only		
17	Cooling fan new making as per sample with casting, machining, drilling, tapping, new hub making and tightening with key ways, cutting alignment and balancing on lathe machine with material.	1	NOS			0.00	INR Zero Only		
18	Rotor and rotor shaft alignment checking on lathe machine and rectification and its alignment setting by cut machining and polishing by stone file and complete balance checking.	1	JOB			0.00	INR Zero Only		
19	End cover housing repairing by CI electrode welding and machining as per bearing size.	2	JOB			0.00	INR Zero Only		
20	Gas heating and cutting grinding etc. work of both end connection points strip bars for old damage bar dismantling from rotor.	45	NOS			0.00	INR Zero Only		
21	Rotor shaft bearing housing repairing electrode welding on bearing fitting place or sleeve making as per bearing size.	2	JOB			0.00	INR Zero Only		
22	Complete motor set dismantling, after repairing work its complete assembling/commissioning with testing, cheking charge	1	JOB			0.00	INR Zero Only		
23	Repairing and setting of terminal box and new making of its cover by iron sheet.	2	NOS			0.00	INR Zero Only		
24	Complete motor coil cleaning ,after cleaning its varnishing/heating,tapping etc.	1	JOB			0.00	INR Zero Only		
25	After repairing and changing of strip bars complete new brazing of both end points by gas heating ,silver rod brazing and copper bars shape making of rotor strip bars after this bars fixing in same slots.	45	NOS			0.00	INR Zero Only		
26	Damage bearing of drive and non drive end removing by puller and gas heating and then new bearing fitting.	2	JOB			0.00	INR Zero Only		
27	Providing and fixing of drive END BEARING NO. N324 ECJ/C3	1	NOS			0.00	INR Zero Only		
28	Providing and fixing of drive NON-END BEARING NO. 6321-C3	1	NOS			0.00	INR Zero Only		
29	PART-C-REPAIRING AND MAINTENANCE OF 168KW/220HP,440V,1485 RPM,INDUCTION MOTOR ATTACHED WITH 500 GPM PUMP UNDER AADOCM DHORI AREA.	1	nos			0.00	INR Zero Only		
30	INDUCTION MOTOR COMPLETE OPENING/DISMANTLING.	1	JOB			0.00	INR Zero Only		
31	ROTOR SHAFT BEARING HOUSING REPAIRING ELECTRODE WELDING ON BEARING FITTING PLACE OR SLEEVE MAKING AS PER BEARING SIZE.	2	JOB			0.00	INR Zero Only		
32	CLEANING REPAIRING AND RESETTING OF ROTOR BAR BY BRAZING WITH ROPOTON ROD AT BOTH ENDS.	60	NOS.			0.00	INR Zero Only		
33	COMPLETE MOTOR SET FITTING THEN TESTING AND COMMISSIONING.	1	JOB			0.00	INR Zero Only		
34	END COVER HOUSING REPAIRING BY CI ELECTRODE WELDING AND MACHINING AS PER BEARING SIZE.	2	JOB			0.00	INR Zero Only		
35	Damage bearing of drive and non drive removing by puller gas heating and then new bearing fitting.	2	JOB			0.00	INR Zero Only		
36	Providing and fixing of drive END BEARING NO. NU 319 ECJ/C3	1	NOS			0.00	INR Zero Only		
37	Providing and fixing of drive NON-END BEARING NO. 6319-C3	1	NOS			0.00	INR Zero Only		
38	SUPERVISION INCIDENTAL& OVERHEAD EXPENSES(A+B+C)	1	nos			0.00	INR Zero Only		
39	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only		
Total in Figures						0.00	INR Zero Only		
Quoted Rate in Words						INR Zero Only			

Name of the Work / Contract No:	"Fresh wiring in D-9 and B-54, Executive hostel at G.M. colony, Dhori Area.
---------------------------------	-----------------------------------------------------------------------------

Category of Bidder (To Be	To Be Entered by Department
---------------------------	-----------------------------

Works Contract

Name of the Bidder/ Bidding Firm / Company :	
----------------------------------------------	--

Select

18

0.00

0.00

0.00

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE in Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/ recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required: Group A a) Bulb point.	42	nos.			0.00	INR Zero Only
2	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/ recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required: Group A b) Tube light point.	17	nos.			0.00	INR Zero Only
3	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/ recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required: Group A c) Fan point.	11	nos.			0.00	INR Zero Only
4	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/ recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required: Group A d) Ex-haust fan point.	4	nos.			0.00	INR Zero Only
5	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/ recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required: Group A e) Call bell point.	1	nos.			0.00	INR Zero Only
6	Supplying and fixing metal box of 150 mm x 75 mm x 60 mm deep (nominal size) on surface in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 3 pin 5/6 amps socket outlet and 5/6 amps piano type switch, connection, painting etc. as required. (For light plugs to be used in non residential buildings).	42	nos.			0.00	INR Zero Only
7	Supplying and fixing metal box of 180 mm x 100 mm x 60 mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 6 pin 5/6 & 15/16 amps socket outlet and 15/16 amps piano type switch, connection, painting etc. as required.	11	nos.			0.00	INR Zero Only
8	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole & neutral.	12	nos.			0.00	INR Zero Only
9	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/isolator). : 6 way, double door.	4	nos.			0.00	INR Zero Only
10	Providing and fixing following capacity TP&N disconnector fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required. 32 Amp TP&N.	3	nos.			0.00	INR Zero Only
11	Supply and fixing of A.C. box.	4	nos.			0.00	INR Zero Only
12	Supplying and drawing following sizes FRLS PVC insulated copper conductor, single core cable in existing surface/ recessed steel/ PVC conduit as required. : 3 x 1.5 sq.mm.	105	Mtrs.			0.00	INR Zero Only
13	Supplying and drawing following sizes FRLS PVC insulated copper conductor, single core cable in existing surface/ recessed steel/ PVC conduit as required. : 3 x 2.5 sq.mm.	268	Mtrs.			0.00	INR Zero Only
14	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required. 2 x 6 sq.mm + 1 x 6 sq.mm earth wire.	156	Mtrs.			0.00	INR Zero Only
15	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required. 2 x 10 sq.mm + 1 x 6 sq.mm earth wire.	58	Mtrs.			0.00	INR Zero Only
16	Providing and fixing following capacity TP&N disconnector fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required. 63 Amp TP&N.	1	nos.			0.00	INR Zero Only
17	Earthing with G.I. earth plate 600 mm x 600 mm x 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long with charcoal/ coke and salt as required.	3	set.			0.00	INR Zero Only
18	Providing and fixing 25 mm x 5 mm dia G.I. strip on surface or in recess for connections etc. as required.	10	Mtrs.			0.00	INR Zero Only
19	Supplying and fixing brass batten/ angle holder including connection etc. as required.	42	nos.			0.00	INR Zero Only
20	Supplying and fixing 3 pin, 5 amps ceiling rose on the existing junction box/ wooden block including connection etc. as required.	28	nos.			0.00	INR Zero Only
21	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only		

Name of the	"Fresh wiring in G.M. Bunglow under G.M. unit, Dhori Area.
-------------	------------------------------------------------------------

	Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Department)	To Be Entered by Department				
ITC Not Available	Works Contract		Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company			Select	18	0.00	0.00	0.00	

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE in Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	6	7	8
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C a) Bulb point	124	points			0.00	INR Zero Only
2	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C b) Tube point	150	points			0.00	INR Zero Only
3	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C c) Fan point	30	points			0.00	INR Zero Only
4	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C d) Ex-haust fan point	14	points			0.00	INR Zero Only
5	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C e) Call bell point	4	Points			0.00	INR Zero Only
6	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 amps modular socket outlet and 5/6 amps modular switch, connection, etc. as required, (for light plugs ton be used in non residential buildings).	105	Each			0.00	INR Zero Only
7	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, connection, etc. as required.	45	Each			0.00	INR Zero Only
8	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/isolator) : 6 way, double door. (for A.C. & other equipments)	20	Each			0.00	INR Zero Only
9	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole & neutral	40	Each			0.00	INR Zero Only
10	Supplying and fixing stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate as required.	30	Each			0.00	INR Zero Only
11	Providing and fixing following capacity TPN&N disconnector fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required : 100 Amp.	2	Each			0.00	INR Zero Only
12	Supplying and drawing following sizes FRLS PVC insulated copper conductor, single core cable in existing surface/ recessed steel/ PVC conduit as required : 3 x 4 sq.mm	985	Mtrs.			0.00	INR Zero Only
13	Supplying and drawing following sizes FRLS PVC insulated copper conductor, single core cable in existing surface/ recessed steel/ PVC conduit as required : 3 x 1.5 sq.mm	867	Mtrs.			0.00	INR Zero Only
14	Supplying and fixing 3 pin, 5 amps ceiling rose on the existing junction box/ wooden block including connection etc. as required.	198	Each			0.00	INR Zero Only
15	Supplying and fixing brass batten/ angle balder including connection etc. as required.	124	Each			0.00	INR Zero Only
16	Earthing with copper earth plate 600 mm x 600 mm x 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	4	Each			0.00	INR Zero Only
17	Supplying, installing, testing and commissioning of following capacity TPN distribution tap off box made of 1.6 mm thick sheet steel enclosure duly painted with powder coating on existing rising mains complete with HRC fuses, interconnections, earthing etc. as required : 63 amps TPN, 8 way.	2	Each			0.00	INR Zero Only
18	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FLRS PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required : 4 x 16 sqmm + 2 x 6 sqmm earth wire.	325	Mtrs.			0.00	INR Zero Only
19	-do- 2 x 6 sqmm + 1 x 6sqmm earth wire.	220	Mtrs.			0.00	INR Zero Only
20	-do- 4 x 25 sqmm for main power connection.	280	Mtrs.			0.00	INR Zero Only
21	Supply of LED bulb 12 watt.	60	Each			0.00	INR Zero Only
22	Providing and fixing 25 mm x 5 mm dia G.I. strip on surface or in recess for connections etc. as required.	80	Mtrs.			0.00	INR Zero Only
23	Supply and fixing of ceiling light 18 watt.	32	Each			0.00	INR Zero Only
24	Supply and fixing of Smart LED 20 watt round wif.	46	Each			0.00	INR Zero Only
25	Supply and fixing of Exhaust fan.	6	Each			0.00	INR Zero Only
26	Supply and fixing of changeover switch.	2	Each			0.00	INR Zero Only
27	Supply and fixing of A.C box	15	Each			0.00	INR Zero Only
28	Supply and providing of Call bell	4	Each			0.00	INR Zero Only
29	Supply and providing of water booster /pressure pump motor 220V 0.75HP.	1	Set.			0.00	INR Zero Only
33	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words				INR Zero Only			

Tender Inviting Authority: Staff officer(E&M), Dhori Area.

Name of the Work / Contract No:	Repairing and maintenance of 2 no 120 HP Motor and 1no 150HP Motor, 550 Volt, 1440- RPM at 4,5,6 incline in respect of Dhori (K) Colliery of Dhori Area.							
.	Category of Services (To Be Selected by Department)		Category of Bidder (To Be	To Be Entered by Department				
ITC Available	Works Contract		Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :			Select	18	0.00	0.00	0.00	

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Motor Washing, heating and varnishing & insulation tapping lead	3	Job			0.00	INR Zero Only
2	Flexible copper terminal lead with glass insulation	18	No			0.00	INR Zero Only
3	New CI casting machining of bearing housing as per shape and size	3	No			0.00	INR Zero Only
4	End cover housing repairing by CI electrode welding and machining as per bearing size	3	No			0.00	INR Zero Only
5	complete opening, fitting after full overhauling, cleaning & both end bearing greasing	3	No			0.00	INR Zero Only
6	Motor rotor shaft both side missed thread repairing and rethreading by full round welding machine and new threading as per standard size	5	No			0.00	INR Zero Only
7	Supply of suitable size copper lug of required rating/size including crimping, connection, fixing etc,	18	No			0.00	INR Zero Only
8	Damaged/old bearing opening by Pooler and gas cutting after opening of bearing new bearing fitting	3	No			0.00	INR Zero Only
9	Rotor shaft bearing place repairing by electrode welding /sleeve making as per bearing size etc.	3	No			0.00	INR Zero Only
10	Gas heating and cutting grinding etc work of both end connection point, strip bars for old damage bar dismantling.	68	No			0.00	INR Zero Only
11	After repairing and changing strips bars complete new breezing and copper bars shape making and fixing small slot grinding machine of breezing point.	68	No			0.00	INR Zero Only
12	Motor rotor alignment checking on lathe machine & true cut machining, polishing	3	No			0.00	INR Zero Only
13	Fabrication of joint box with required material as per shape & size	1	No			0.00	INR Zero Only
14	Cracked fan cover repairing cost	1	No			0.00	INR Zero Only
15	Providing and fixing of missing/damage bolt as per required size	30	No			0.00	INR Zero Only
16	Supervision incidental over head expenses 15% the estimated value	1	Job			0.00	INR Zero Only
17	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					

Tender Inviting Authority: Staff officer(E&M), Dhori Area.

Name of the Work / Contract No:

"Repairing of Capacitor Bank 11 KV grade at 33 KV/11 KV Main Regional Sub station, MRSS, under G. M. Unit, Dhori Area."

Category of Services (To Be Selected by Department)

Category of Bidder (To Be)

To Be Entered by Department

ITC Available

Works Contract

Bidder's Status (Mandatory)

Select

Rate of GST (in %)

18

Total GST(in Rs.)

0.00

GST to be Paid By Bidder (in Rs.)

0.00

GST to be Paid By CIL/Subsidiary (in Rs.)

0.00

Name of the Bidder/ Bidding Firm / Company :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Providing of 240 Kvar, 11KV 50Hz,3-Ph, Capacitor	02	Nos.			0.00	INR Zero Only
2	Providing of 360 Kvar,11KV, 50Hz 3-Ph, Capacitor	04	Nos.			0.00	INR Zero Only
3	Providing of H.R.C. Fuse, 11KV, 40 Amp.	06	Nos.			0.00	INR Zero Only
4	Providing of H.R.C. Fuse, 11KV, 60 Amp.	06	Nos.			0.00	INR Zero Only
5	Providing of PT per VCB (Complete set)	01	unit			0.00	INR Zero Only
6	Labour charge for fixing of capacitor bank % of SR. No: 1, 2, 3, and 4	1	nos			0.00	INR Zero Only
7	Testing and commissioning of whole capacitor bank along with electrical connection % of SR. No: 1, 2, 3, 4 and 5 with required consumables.	1	nos			0.00	INR Zero Only
8	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					

Item Rate BoQ

Tender Inviting Authority: Staff officer(E&M), Dhori Area.								
Name of the Work / Contract No:	Repairing and maintainence of two range of 4" dia G.I. delivery pipe line out at 7/8 & 4/5/6 incline under Dhori (K) colliery for smooth de watering in uncoming monsoon supply and fixing of 2",1.5" and 1" dia pipe line for dust supression and roof bolting in new panels of both lincline at Dhori (K) colliery.							
	Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract			Bidder's Status (Mandatory) Select	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :					18	0.00	0.00	0.00
PRICE SCHEDULE								
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #	
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words	
1	2	3	4	5	6	7	8	
1	Part (A) Repairing and maintainence of two range 4" dia G.I. delivery pipe line and outside at 7/8 and 4/5/6 incline.	1	Nos			0.00	INR Zero Only	
2	Dismantaling of old and damaged pipe line delivery	350	Mtr.			0.00	INR Zero Only	
3	Transportation of GI pipe 4"size from incline to surface	60	Nos			0.00	INR Zero Only	
4	Transportation of GI pipe 4"size from surface to incline	60	Nos			0.00	INR Zero Only	
5	Fabrication of 4" G.I. bend	8	Nos			0.00	INR Zero Only	
6	Fitting of bend,non return valve, sulice valve and foot valve,	5	Set			0.00	INR Zero Only	
7	Dismantaling of bend,non return valve, sulice valve and foot valve,	5	Nos			0.00	INR Zero Only	
8	Supply of G.I. flenge	80	Nos			0.00	INR Zero Only	
9	Laying of pipe line 4" dia pipe line	350	Mtr.			0.00	INR Zero Only	
10	Cutting by oxygen and DA of G.I. pipe both side 4" approx for bending or where as requires (100x4"x3.14)	1256	inch			0.00	INR Zero Only	
11	Welding of flenge with pipe 4" double layer (2.80X4"diaX3.14)	2009.6	Inch			0.00	INR Zero Only	
12	G.I. nuts and bolts	50	Kg			0.00	INR Zero Only	
13	PART (B) Supply and fixing of 2",1.5" and 1" dia pipeline for dust supression and roof bolting	1	Nos			0.00	INR Zero Only	
14	Supply of 2" dia G.I. pipe for 4,5,6 incline (34 Nos.)	200	Unit			0.00	INR Zero Only	
15	Providing 2" pipe flange.	50	M			0.00	INR Zero Only	
16	Nepple 4" long 1/2" dia	20	Nos			0.00	INR Zero Only	
17	Valve 1/2 "	10	Nos			0.00	INR Zero Only	
18	Welding of flenge with pipe 2" and damaged part of pipe	50	Nos			0.00	INR Zero Only	
19	Cutting of pipe where as required.	100	inch			0.00	INR Zero Only	
20	Cutting and making of Rubber packing	64	inch			0.00	INR Zero Only	
21	Transportation of 2" dia pipes manually from surface to incline	50	Nos			0.00	INR Zero Only	
22	Assembling of 2" dia GI pipe line in different dip.	200	Nos			0.00	INR Zero Only	
23	Reducer 2"/1.5"	1	M			0.00	INR Zero Only	
24	Sulice valve 2"	1	Nos			0.00	INR Zero Only	
25	Supply of 1.5 " dia G.I. pipe for 4,5,6 incline (16 Nos)	120	Nos			0.00	INR Zero Only	
26	Providing 1.5 " pipe socket	10	M			0.00	INR Zero Only	
27	Providing 1.5 " pipe T socket	6	Nos			0.00	INR Zero Only	
28	Nepple 4" long 1/2" dia	12	Nos			0.00	INR Zero Only	
29	Valve 1/2 "	6	Nos			0.00	INR Zero Only	
30	Reducer 1.5"	1	Nos			0.00	INR Zero Only	

31	1.5" union	1	Nos			0.00	INR Zero Only
32	Transportation of 1.5" dia pipes manually from surface to incline	16	Nos			0.00	INR Zero Only
33	Assembling of 1.5" dia GI pipe line in different dip.	120	Nos			0.00	INR Zero Only
34	Supply of 1" dia G.I. pipe for 4,5,6 incline (45)	270	M			0.00	INR Zero Only
35	Providing 1" pipe socket	30	Nos			0.00	INR Zero Only
36	Providing 1" pipe socket T type	15	Nos			0.00	INR Zero Only
37	Providing 1" union	5	Nos			0.00	INR Zero Only
38	Nepple 4"	30	Nos			0.00	INR Zero Only
39	Valve 3/4	15	Nos			0.00	INR Zero Only
40	Transportation of 1" dia pipes manually from surface to incline	45	Nos			0.00	INR Zero Only
41	Assembling of 1" dia GI pipe line in different dip.	272	M			0.00	INR Zero Only
42	Supervision, Accidental & contractor OH (A+B)	1	Nos			0.00	INR Zero Only
43	underground allowence on item no (A+B)) (1 , 5 , 6 , 8 , 9 ,19,21,22,, 32,33,,40,41, and 42)	1	Nos			0.00	INR Zero Only
44	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					

Tender Inviting Authority: Staff officer(E&M), Dhori Area.

Name of the Work / Contract No:	*Repairing of 4 nos. D.G. set att Central Hospital, Dhori and CISF Raja Bunglow, G.M. office under G.M. unit, Dhori Area.					
	Category of Services (To Be Selected by Department)		Category of Bidder (To Be)	To Be Entered by Department		
ITC Not Available	Works Contract		Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	18	0.00	0.00
						0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Part A : Raja Bunglow CISF (Kirlosker make)	1	nos			0.00	INR Zero Only
2	Providing & fixing of oil seal.	1	No.			0.00	INR Zero Only
3	Fuel pump packing kit assly.	1	No.			0.00	INR Zero Only
4	Providing & fixing of coolant.	5	Ltrs.			0.00	INR Zero Only
5	Providing & fixing Anaboard.	1	No.			0.00	INR Zero Only
6	Providing & fixing lock.	1	No.			0.00	INR Zero Only
7	Providing & fixing Battery terminal socket.	1	Set.			0.00	INR Zero Only
8	Providing & fixing Air cleaner element.	1	No.			0.00	INR Zero Only
9	Repairing of fuel pump assly.	1	No.			0.00	INR Zero Only
10	Providing & fixing of 'V' belt.	2	Nos.			0.00	INR Zero Only
11	Repairing of self.	1	Job.			0.00	INR Zero Only
12	Supply & fixing Diesel pipe assly.	1	No.			0.00	INR Zero Only
13	Servicing charge.	1	No.			0.00	INR Zero Only
14	Part B : CHD (Kirlosker make)	1	nos			0.00	INR Zero Only
15	Providing & fixing Automatic system with display controller 100 KVA.	1	Set.			0.00	INR Zero Only
16	Providing & fixing VMR operation 100 KVA.	1	Set.			0.00	INR Zero Only
17	Providing & fixing Earth relay overload 100 KVA.	1	No.			0.00	INR Zero Only
18	Providing & fixing 11 pin relay operation 100KVA.	2	Nos.			0.00	INR Zero Only
19	Providing & fixing 11 pin relay holder 100 KVA	2	Nos.			0.00	INR Zero Only
20	Providing & fixing fuel filter.	1	No.			0.00	INR Zero Only
21	Providing & fixing Air cleaner element 100 KVA.	1	No.			0.00	INR Zero Only
22	Servicing charge.	1	No.			0.00	INR Zero Only
23	Part C : G.M. office (Ashok Leyland)	1	nos			0.00	INR Zero Only
24	Providing & fixing mobil filter assembly 125 KVA.	1	No.			0.00	INR Zero Only
25	Providing & fixing Diesel filter assembly 125 KVA.	1	No.			0.00	INR Zero Only
26	Providing & fixing Air cleaner assembly 125 KVA.	1	No.			0.00	INR Zero Only
27	Providing & fixing Automatic system controller relay 125 KVA.	1	No.			0.00	INR Zero Only
28	Providing & fixing contactor relay.	1	No.			0.00	INR Zero Only
29	Servicing charge.	1	No.			0.00	INR Zero Only
30	Part D : G.M. office (Escort)	1	nos			0.00	INR Zero Only
31	Providing & fixing mobil filter assembly 50 KVA.	1	No.			0.00	INR Zero Only
32	Providing & fixing Diesel filter assembly 50 KVA.	1	No.			0.00	INR Zero Only
33	Air cleaner element assembly 50 KVA.	1	No.			0.00	INR Zero Only
34	Providing & fixing contractor 50 KVA.	1	No.			0.00	INR Zero Only
35	Servicing charge.	1	No.			0.00	INR Zero Only
36	Supervision, incidental & overhead expenses	1	Job.			0.00	INR Zero Only
37	Total Impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					

Item Rate BoQ

Tender Inviting Authority: Staff officer(E&M), Dhori Area.							
Name of the Work / Contract No:	"Providing and fixing of decorative garden light sets at G.M. colony and G.M. Bunglow garden under G.M. unit, Dhori Area.						
.	Category of Services (To Be Selected by Department)		Category of Bidder (To Be)	To Be Entered by Department			
ITC Not Available	Works Contract		Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	18	0.00	0.00	0.00
<p align="center">PRICE SCHEDULE</p> <p align="center">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</p>							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Supply and Providing of G.I. pipe (medium class) : 50mm dia.	245	Mtrs.			0.00	INR Zero Only
2	Providing and making steel pole collar with cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) of specified size and shape including form work, plastering if specified size and shape including form work, plastering if required, curing etc as required. (volume of pole/pipe not to be deducted) 98 x 0.60 x 0.60 x 1.20 = 42.34 cum	42.34	Cum			0.00	INR Zero Only
3	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole & neutral.	98	Nos.			0.00	INR Zero Only
4	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required : 4 x 10 sq.mm + 2 x 6 sq.mm earth wire.	1170	Mtrs.			0.00	INR Zero Only
5	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required : 2 x 2.5 sq.mm + 1 x 2.5 sq.mm earth wire.	670	Mtrs.			0.00	INR Zero Only
6	Supplying and fixing of following sizes of medium class PVC conduit, along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required. : 25 mm.	700	Mtrs.			0.00	INR Zero Only
7	Excavation for foundation in soft soil including dressing of sides and ramming of bottoms, lift upto 1.5m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 metres. 1840.00 x 0.60 x 0.60	662	Cum			0.00	INR Zero Only
8	Supply of garden light (inbuilt LED type 20 watt.)	98	Nos.			0.00	INR Zero Only
9	Supply of Rope light.	686	Mtrs.			0.00	INR Zero Only
10	Supplying, installing, testing and commissioning of following capacity TPN distribution tap off box made of 1.6 mm thick sheet steel enclosure duly painted with powder coating on existing rising mains complete with HRC fuses, interconnections, earthing etc. as required. : 32 amps TPN, 4 way.	4	Nos.			0.00	INR Zero Only
11	Supply of changeover switch.	2	Nos.			0.00	INR Zero Only
12	Labour cost for fixing of garden light.	98	Nos.			0.00	INR Zero Only
13	Labour cost for fixing of Rope light.	686	Mtrs.			0.00	INR Zero Only
14	Filling available excavated earth (excluding rock) in trenches, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 metres.	607	Cum			0.00	INR Zero Only
15	Dismantling of pole in cement concrete foundation etc. as required.	8	Nos.			0.00	INR Zero Only
16	Erection of steel tubular pole in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling and secured with holding clamps, bolts, nuts etc as required	8	nos.			0.00	INR Zero Only
18	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					

Item Rate BoQ

Tender Inviting Authority: Staff officer(E&M), Dhori Area.							
Name of the Work / Contract No:	"Erection of heavy lighting conductor at GM office, Area account office and Raja Bunglow under GM unit, Dhori Area."						
.	Category of Services (To Be Selected by Department)		Category of Bidder (To Be)	To Be Entered by Department			
ITC Not Available	Works Contract		Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	18	0.00	0.00	0.00
<p align="center">PRICE SCHEDULE</p> <p align="center">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</p>							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Erection of RCC/PCC pole of following length in brick ballast and ramming the foundation, finishing with 150 mm thick cement concrete (1:3:6) layer on top with including excavation and re-filling etc. as required : Above 11.0 metre and upto 13.0 metre.	10	nos			0.00	INR Zero Only
2	Supplying of channel iron 75 mm × 40 mm × 6 mm (7.14 kg per metre) cross arm for 2 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for pole line clamps etc (as per drawing) and painting with finished paint as required.	40	nos			0.00	INR Zero Only
3	Earthing with copper earth plate 600 mm × 600 mm × 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. (but without charcoal/coke and salt) as required.	10	nos			0.00	INR Zero Only
4	Supplying of aluminium decorative conductor finial, made of 25 mm dia 300 mm long copper tube, having single prong at top with base plate and G.I. base plate including painting with copper paint etc as required.	10	nos			0.00	INR Zero Only
5	Providing and fixing 25 mm × 5 mm G.I. strip on surface or in recess for loop earthing as required.	150	mtr			0.00	INR Zero Only
6	Providing and fixing 25 mm × 5 mm copper strip on surface or in recess for loop earthing as required.	24	mtr			0.00	INR Zero Only
7	Supplying of iron clamps of galvanised 'D' iron complete with shackle insulator (75 mm × 90 mm), G.I. bolts, nuts and washers, coach screw etc. as required.	10	set			0.00	INR Zero Only
8	Applying priming coat: With ready mixed red oxide zinc Chromate primer of approved brand and manufacture on steel galvanised iron/steel works.	32.55	sqm			0.00	INR Zero Only
9	Painting with aluminium paint of approved brand and manufacture to give an even shade: Two or more coats on new work. Quantity: Thirty-Two Point Five (32.5) square metre	32.55	sqm			0.00	INR Zero Only
10	Transporting of pole (Unit store to site place).	10	nos			0.00	INR Zero Only
11	Erection of angle iron/ channel iron cross arm on wood/RCC/PCC/steel tubular/rail pole etc. as required.	40	nos			0.00	INR Zero Only
12	Providing and fixing 4.00 mm dia copper wire on surface or in recess for loop earthing as required.	425	mtr			0.00	INR Zero Only
13	Supplying and erection of 11 KV pin insulator complete with large steel head G.I. pin, nuts, washers etc. as required.	40	nos			0.00	INR Zero Only
14	Providing and making steel pole collar with cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) of specified size and shape including form work, plastering if specified size and shape including form work, plastering if required, curing etc. as required. (Volume of pole/pipe not to be deducted).	1.27	cum			0.00	INR Zero Only
18	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					