

Departmental Estimate for repairing of Hoist cylinder, Tie rod, Steering cylinder both sides of BH60M Dumper Sl. no. 60777 at Jharkhand OCP.

sl. no.	Description	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1	Industrial gas Oxygen Gas (7 CuM)	4	NO		
2	Industrial gas DA Gas (7 CuM)	2	NO		
3	Gauging electrode (L-602)	6	KG		
4	Grinding stone for surface finishing. (Size-4")	8	NO		
5	Steel electrode for jointing and material filling. (Lomet205)	15	KG		
6	Seal kit (955HC00017)	2	NO		
7	Ball Stud (57540001330)	6	NO		
8	Racer (958SS11197)	12	NO		
9	Seal Kit (955HC00025)	2	NO		
10	Bushing (958HS13315)	2	NO		
11	Bushing (958HS13331)	2	NO		
12	Hiring Cost of Welding machine, Jack and special tools tackles etc	5	DAY		
13	Supervisor - (01 person X 05 days)	5	SFT		
14	Welder - (02 person X 05 days)	10	SFT		
15	Fitter - (02 person X 05 days)	10	SFT		
16	Helper - (03 person X 05 days)	15	SFT		
sub total					
Contractor's profit@10%					
Total					
GST @18% of total cost					
Total Amount					
GRAND TOTAL (Rounding Off)					