

Tender Inviting Authority: Staff officer (E&M), Amrapali- Chandragupta Area, CCL						
Name of the Work / Contract No:	Re-wiring of following quarters occupied by employees of Amrapali OCP under A-C Area 1. MQ-267 at Bachra. 2. H/B-39 at Old Mines colony Bachra 3. 193 at 64 colony Bachra 4. MQ-395 at Bachra 5. MQ-452 at 122 colony Bachra 6. B-14 (PPR) Subhas Nagar Dakra 7. MQ-140 Basant Vihar Colony				NIT No: G.M.(A-C)/S.O.(E&M)/e-NIT/25-26/17 ; Dated: 25.08.2025	
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)				
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with piano type switch, phenolic laminated sheet, suitable size MS box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group A	116.000	Points		0.00	INR Zero Only
2	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire	335.000	Mtr.		0.00	INR Zero Only
3	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	455.00	Mtr.		0.00	INR Zero Only

4	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required.	22.00	Each		0.00	INR Zero Only
5	Supplying and fixing Cable End Box (Loose Wire Box) suitable for following single pole and neutral, sheet steel, MCB distribution board, 240 Volts, on surface/ recess, complete with testing and commissioning etc. as required. For 06 way, Double door SPN MCBDB	7.00	Each		0.00	INR Zero Only
6	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit alongwith 1 No. 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	430.00	Mtr.		0.00	INR Zero Only
7	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	15.00	Each		0.00	INR Zero Only
8	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	30.00	Each		0.00	INR Zero Only
9	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole and neutral	14.00	Each		0.00	INR Zero Only
10	Supplying & fixing suitable size GI box with modular plate and cover in front on surface or in recess including providing and fixing 25 A modular socket outlet and 25 A modular SP MCB, "C" curve including connections, painting etc. as required.	8.00	Each		0.00	INR Zero Only
11	Installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required. 510 mm sweep	8.00	Each		0.00	INR Zero Only
12	Installation, testing and commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable etc. as required.	9.00	Each		0.00	INR Zero Only
13	Providing and fixing 50 mm dia X 3.2 metres G.I. pipe (including accessories) complete with 50 mm X 50 mm X 6 mm angle iron bracket on wall and 75 mm X 90 mm shackle insulator with straps for house service connection including painting the angle and flat iron with primer and finish paint etc. as required.	3.00	Each		0.00	INR Zero Only
14	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	