

Tender Inviting Authority: Project Engineer (E&M), Gidi-W Project, Argada area, CCL.

Name of the Work / Contract No:		Dismantling and reerection of Fixed Type High Mast Lightning Tower installed at Gidi-Washery Under Argada Area.		NIT No: PE(E&M)/GDW/e-NIT/25-26/03		Dated: 26.08.2025	
Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)					
ITC Available	Works Contract	Bidder's Status (Mandatory)		Total GST (in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select		0.00	0.00	0.00	

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
SL No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in Foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plane), including dressing of sides and ramming of bottoms, lift upto 1.5 m including getting out of excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m. All kinds of soil. (3.2 Mtr. X 3.2 Mtr X3.2 Mtr=32.77)	32.77	Cum		0.00	INR Zero Only
2	Filling available excavated earth (including rock) in trenches ,plinth, sides of foundation etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering lead upto 50 m and lift upto 1.5 m	26.78	Cum		0.00	INR Zero Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering All work upto plinth: 1:4:8(1 cement: 4 coarse sand (Zone-III): 8 graded stone aggregate 40 mm (nominal size) (3.2 Mtr x 3.2 Mtr x 0.10 Mtr = 1.02)	1.02	Cum		0.00	INR Zero Only
4	Providing and laying in position specified grade of reinforced cement Concrete, excluding the cost of centering, shuttering, finishing and reinforcement- All work upto plinth: 1:1.5:3 (1 cement: 1.5 coarse sand(Zone-III): 3 graded stone aggregate 20 mm nominal size) (3.2 Mtr x 3.2 Mtr x 0.24 Mtr = 2.45)	2.45	Cum		0.00	INR Zero Only
5	Centering and Shuttering including strutting, propping etc. and removal of form of foundations, footings, bases of columns etc. for mass concrete. (1.9 Mtr x 1 Mtr = 1.9)	1.90	Sqm.		0.00	INR Zero Only
6	Centering and Shuttering including strutting,propping etc. and removal of form of Columns, Pillars, Piers, Abutments, Posts and Struts. (2.9 Mtr x 1 Mtr = 2.9)	2.90	Sqm.		0.00	INR Zero Only
7	Reinforcement for R.C.C work including straightning,cutting, bending, placing in position and binding all complete. Thermo Mechanically Treated bars of grade Fe-500D or more	150.00	Kg		0.00	INR Zero Only
8	Dismantling, re-erection & commissioning of Fixed Type High Mast Lightning Tower Upto 16 Mtrs.	1.00	Job		0.00	INR Zero Only
9	Cost of Fondation Bolts for fixing of lightning Tower (M30 x 1000mm)	16.00	Nos		0.00	INR Zero Only
10	Supply and Fixing of Power Centre Control Panel, ISI Marked	1.00	Nos		0.00	INR Zero Only
11	Supply and Fixing of 6 Sq.mm 2 Core PVC insulated FRLS Multi- Stranded Copper Conductor.	35.00	Mtr		0.00	INR Zero Only
12	Reapairing Of LED Light of High Mast Lightning Tower	7.00	Nos		0.00	INR Zero Only
13	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words			INR Zero Only			