

Tender Inviting Authority:	SO(E&M)/ H					
Name of the Work / Contract No:	Dismantling of LT line and erection of 3.3KV OH line in mines and Charhi siding of Tapin South OCP under Hazaribagh area					
.	Category of Services ( To Be Selected by Department)	Category of Bidder ( To Be Selected by Bidder)	To Be Entered by Department			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Erection of steel tubular or rail pole strut in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size ) foundation including excavation and refilling and secured with holding clamps, bolts, nuts, etc. as required.	26	nos.			0.00	INR Zero Only
2	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, turn buckle ( 20 mm X 60 cm), 7/ 4.00 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size ) foundation including excavation and refilling etc. as required.	14	nos.			0.00	INR Zero Only
3	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above including binding etc. as required.	1265	Kg			0.00	INR Zero Only
4	Dismantling of overhead lines comprising of copper/aluminium overhead conductor, G.I.wire, crossarms, insulators etc.as required.	1472	Kg			0.00	INR Zero Only
5	Erection of angle iron/channel iron cross arm on wood/RCC/PCC/ steel tubular/rail pole etc.as required	26	nos.			0.00	INR Zero Only
6	Supplying and erection of 11 KV disc insulator for 11 KV over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required.	46	nos.			0.00	INR Zero Only
7	Supplying and erection of 11 KV pin insulator complete with large steel head G.I. pin, nuts, washers etc. as required.	24	nos.			0.00	INR Zero Only
8	Dismantling of pole/streetlight standard/strut embedded in cement concrete foundation etc. as required.	19	nos.			0.00	INR Zero Only
9	Erection of cradle guard as required.	5	each			0.00	INR Zero Only
10	Supply of Stay wire ( 7/3.15 mm dia) for earth continuity ( 990 Mtr X 0.469 Kg/ Mtrs X 1.05 =488 Kg )	488	Kg			0.00	INR Zero Only
11	Erection of Stay wire ( 7/3.15 mm dia) for earth continuity.	488	Kg			0.00	INR Zero Only
12	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	4	nos.			0.00	INR Zero Only
13	providing and fixing of 25sq mm Al wire for earthing connection	60	mtr			0.00	INR Zero Only
14	Making of cradle guard by supplying 6 SWG GI wire	5	nos.			0.00	INR Zero Only
15	installation of Departmentally supplied vertical type 11KV GOAB	1	nos.			0.00	INR Zero Only
16	Installation of 50KVA departmentally supplied transformer on pole	1	nos.			0.00	INR Zero Only
17	providing of 10 sq mm Cu wire	200	mtr			0.00	INR Zero Only
18	Supplying of two lengths of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) double pole cross arm for three wire 11KV over head line conductors complete with through bolts and nuts for clamping to the poles, 50 mm X 6 mm M.S. flats welded on one side to the channel iron and with bolts and nuts on the other side for tying the cross arms together, including drilling holes for insulator pins/ fittings, bolts, nuts and washers etc (as per drawing) and painting with primer and finish paint as required.	4	nos.			0.00	INR Zero Only
19	Supplying, installing, testing and commissioning of 200Amp capacity End Feed Unit made of 1.6mm thick sheet steel enclosure duly painted with powder coating to existing rising mains complete with TPN disconnecter FSU and HRC fuses, mounting stands, cable end box, brass compression gland, connections, earthing etc. as required.	2	nos.			0.00	INR Zero Only
20	Supplying and making straight through cable jointing with heat shrinkable jointing kit complete with all accessories including ferrules suitable for following size of 3 core, XLPE aluminium conductor cable of 11 KV grade as required: 70 Sqmm	1	nos.			0.00	INR Zero Only
21	Total impact of GST for the purpose of CTC	1.00	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					