

Validate		Print		Help		Percentage BoQ	
Tender Inviting Authority: Staff Officer(Civil), Magadh-Sanghmitra Area							
Name of Work : Providing and Fixing barbed wire fencing around coal stocks under Magadh OCP of Magadh-Sanghmitra Area. (e NIT No. 32 of 2025-26)							
		Category of Services (To Be Selected by Department)		Category of Bidder(To Be Selected by Bidder)		To Be Entered by Department	
ITC Available		Works Contract		Bidder's Status (Mandatory)		Rate of GST (in %)	
Name of the Bidder/ Bidding Firm / Company :				Select		18.00	
						0.00	
						0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #		TEXT #		NUMBER #		TEXT #	
Sl. No.		Item Description		Quantity		Units	
				Estimated Rate in Rs. P		TOTAL AMOUNT in Rs. P	
1		2		3		4	
1		Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains not exceeding 1.5 m in width or 10 sqm on plan including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed within a lead of 50m.		1528.74		cum	
2		Supplying at site: R.C.C. Standards post/ struts/ rails/ pales of mix 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone sggregate 12.5mm nominal size) with wooden plugs or 6mm bar nibs wherever required as per direction of Engineer-in-charge (cost of eart works in excavation, concrete works in foundation to be paid separately).		80.46		cum	
3		Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size derived from natural sources)		301.72		cum	
4		Fencing with R.C.C. post placed at required distance, embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post one side only, provided with horizontal lines and two diagonals of barbed wire 9.38 kg per 100 metres (min) between the two posts fitted and fixed with G.I. staples on wooden plugs or G.I. binding wire tied to 6 mm bar nibs fixed while casting the post (cost of R.C.C. posts, struts, earth work and concrete to be paid for separately) :- Payment to be made per metre cost of total length of barbed wire used.:With G. I. barbed wire.		31290.00		metre	
5		White washing with lime to give an even shade : New work (three or more coats)		1609.20		sqm	
6		Total impact of GST for the purpose of CTC		1.000		Nos	
Total in Figures						4692304.86	
Quoted Rate in Figures				Select		0.00	
Quoted Rate in Words						INR Zero Only	