

Tender Inviting Authority: Staff Officer(Civil), Rajhara Area.						
Name of Work: Cleaning of sludge in near by area of Coal stock and Cutting of drain & Laying of hume pipe at new site at TTK OCP,Rajhara area						
	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00	
<p align="center">PRICE SCHEDULE</p> <p>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</p>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Excavation inMarshySoil (Excavation for roadway inmarshysoil withhydraulic excavator 0.9 cumbucket capacity including cuttingand loading in tippers and disposalwith inall liftsand leadupto1000metres, trimmingof bottomandside slopes in accordance with requirements of lines, grades and cross sections.)	4245.000	cum	84	356580.00	INR Three Lakh Fifty Six Thousand Five Hundred & Eighty Only
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in charge. 2.6.1 All kinds of soil	990.000	cum	128.05	126769.50	INR One Lakh Twenty Six Thousand Seven Hundred & Sixty Nine and Paise Fifty Only
3	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete1200 mm dia RCC pipes. (Laying by manual/ machanical means) 1 metre 8426.75	37.500	m	8426.75	316003.13	INR Three Lakh Sixteen Thousand & Three and Paise Twelve Only

4	Filling available excavated earth(excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and for all lift 1 cum 114.40	50.000	cum	114.4	5720.00	INR Five Thousand Seven Hundred & Twenty Only
5	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					805072.63	INR Eight Lakh Five Thousand & Seventy Two and Paise Sixty Two Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words						INR Zero Only