

Tender Inviting Authority:STAFF OFFICER CIVIL

Name of Work: Provision of barbed wire fencing with RCC posts at mine edge near Duru Kasmar of PEOCP, Hazaribagh Area

.	Category of Services (To Be Selected by Department)	Category of Bidder( To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Item Description/ Heading					
1.01	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	36.28	Cum	188.45	6836.97	INR Six Thousand Eight Hundred & Thirty Six and Paise Ninety Seven Only
1.02	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	34.02	Cum	5916.00	201262.32	INR Two Lakh One Thousand Two Hundred & Sixty Two and Paise Thirty Two Only
1.03	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	9.07	Cum	7365.50	66805.09	INR Sixty Six Thousand Eight Hundred & Five and Paise Nine Only
1.04	Centering and shuttering including strutting, propping etc. and removal of form for : Columns, Pillars, Piers, Abutments, Posts and Struts.	192.78	Sqm	621.80	119870.60	INR One Lakh Nineteen Thousand Eight Hundred & Seventy and Paise Sixty Only
1.05	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level. Thermo-Mechanically Treated bars.	634.90	Kg	75.85	48157.17	INR Forty Eight Thousand One Hundred & Fifty Seven and Paise Sixteen Only

1.06	Fencing with R.C.C. post placed at required distance, embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post one side only, provided with horizontal lines and two diagonals of barbed wire weighing 9.38 kg per 100metres (minimum), between the two posts fitted and fixed with G.I. staples on wooden plugs or G.I. binding wire tied to 6 mm bar nibs fixed while casting the post (cost of R.C.C. posts, struts, earth work and concrete to be paid for separately) :- Payment to be made per metre cost of total length of barbed wire used. With G.I. barbed wire	5669.00	m	10.25	58107.25	INR Fifty Eight Thousand One Hundred & Seven and Paise Twenty Five Only
2.00	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	0.00	0.00	INR Zero Only
<b>Total in Figures</b>					501039.39	INR Five Lakh One Thousand &Thirty Nine and Paise Thirty Nine Only
<b>Quoted Rate in Figures</b>			Select		0.00	INR Zero Only
<b>Quoted Rate in Words</b>		INR Zero Only				