

Tender Inviting Authority: Staff officer (E&M), Amrapali- Chandragupta Area, CCL						
Name of the Work / Contract No:	Shifting of LT Overhead Line Bewteen filling point and coal stock -49 for widening of light vehicle road at Amrapali OCP under A-C Area				NIT No: G.M.(A-C)/S.O.(E&M)/e-NIT/25-26/20 ; Dated: 15.09.2025	
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Dismantling of pole/ street light standard/ strut embedded in cement concrete foundation etc. as required.	14.000	Each		0.00	INR Zero Only
2	Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required. Above 10.00 metre and upto 12.00 metre	16.000	Each		0.00	INR Zero Only
3	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, turn buckle (20 mm X 60 cm), 7/ 4.00 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	4.00	Each		0.00	INR Zero Only
4	Erection of all aluminium conductor of 7/1.96 mm to 7/3.10 mm diameter including binding etc. as required.	417.76	Kg		0.00	INR Zero Only
5	Dismantling of over head lines comprising of copper/ aluminium over head conductor, G.I. wire, cross arms, insulators etc. as required.	417.76	Kg		0.00	INR Zero Only

6	Supplying and erection of 75 mm X 90 mm shackle insulator with G. I. Bolt, nuts and straps etc. as required .	12.00	Set		0.00	INR Zero Only
7	Supplying and erection of 100 mm X 65 mm pin insulator complete with G. I. Spindle and nuts etc. as required .	8.00	Set		0.00	INR Zero Only
8	Erection of cradle guard as required.	3.00	Each		0.00	INR Zero Only
9	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing as required.	850.00	Mtr.		0.00	INR Zero Only
10	Supplying of two lengths of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) double pole cross arm for three wire 11KV over head line conductors complete with through bolts and nuts for clamping to the poles, 50 mm X 6 mm M.S. flats welded on one side to the channel iron and with bolts and nuts on the other side for tying the cross arms together, including drilling holes for insulator pins/ fittings, bolts, nuts and washers etc (as per drawing) and painting with primer and finish paint as required.	2.00	Set		0.00	INR Zero Only
11	Erection of angle iron/ channel iron cross arm on wood/ RCC/ PCC/ steel tubular/ rail pole etc. as required.	30.00	Each		0.00	INR Zero Only
12	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	2.00	Each		0.00	INR Zero Only
13	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	