

Validate		Print		Help		Percentage BoQ	
Tender Inviting Authority: Staff Officer (Civil),CCL, Dhori Area							
Name of Work:- Making of 18 (Eighteen) nos. of Isolation Stopping and 2 (Two) nos. of preparatory stopping for proposed depillaring Panel 'O' in 4,5,6, Incline & Panel 'L' in 7&8 Incline of Dhori(K) Colliery .							
Category of Services (To Be Selected by Department)		Category of Bidder(To Be Selected by Bidder)		To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)		Rate of GST (in %)		GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select		18.00		0.00	0.00
<p align="center">PRICE SCHEDULE</p> <p align="center">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</p>							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #	
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words	
1	2	3	4	5	6	7	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50 m and lift upto 1.5 m, disposed earth to be levelled and neatly dressed:Ordinary rock	86.4	cum	370.97	32051.81	INR Thirty Two Thousand & Fifty One and Paise Eighty One Only	
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50 m and lift upto 1.5 m, disposed earth to be levelled and neatly dressed:Hard Rock blasting prohibited)	71.28	cum	1075.59	76668.06	INR Seventy Six Thousand Six Hundred & Sixty Eight and Paise Six Only	
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	146.64	cum	5776.14	847013.17	INR Eight Lakh Forty Seven Thousand & Thirteen and Paise Seventeen Only	
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	241	cum	7275.14	1753308.74	INR Seventeen Lakh Fifty Three Thousand Three Hundred & Eight and Paise Seventy Four Only	
5	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand) .	677.88	sqm	272.48	184708.74	INR One Lakh Eighty Four Thousand Seven Hundred & Eight and Paise Seventy Four Only	

6	White washing with lime to give an even shade :New work (three or more coats)	677.88	sqm	30.6	20743.13	INR Twenty Thousand Seven Hundred & Forty Three and Paise Thirteen Only
7	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					2914493.64	INR Twenty Nine Lakh Fourteen Thousand Four Hundred & Ninety Three and Paise Sixty Four Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				