

ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Wiring for light point/fan point/exhaust fan point/call bell point with 1.5 sq.mm FR PVC insulated copper Conductor single core cable in surface/Recessed PVC conduit, with Modular type Switch, phenolic laminated sheet, Suitable size M.S/PVC box and earthing the Point with 1.5sqmm. FR PVC insulated Copper conductor single core cable etc. as required. (Group –"B")	143	PT			0.00	INR Zero Only
1.02	Wiring for circuit/sub main wiring along with earth wire with the following sizes of PVC insulated copper conductor, single Core cable in surface/recessed PVC Conduit as required (2x1.5Sq.mm+ 1.5sq.mm earth wire)	220	MTR			0.00	INR Zero Only
1.03	Wiring for circuit/sub main wiring along with earth wire with the following sizes of PVC insulated copper conductor, single Core cable in surface/recessed PVC Conduit as required (2x2.5 Sq.mm+ 2.5sq.mm earth wire)	329	MTR			0.00	INR Zero Only
1.04	Wiring for circuit/sub main wiring along with earth wire with the following sizes of PVC insulated copper conductor, single Core cable in surface/recessed PVCConduit as required (2x 4Sq.mm + 1x 4 sq.mm earth wire)	123	MTR			0.00	INR Zero Only
1.05	Supply & fixing 5 Amps. To 32Amps. Rating 240/415V. "C" curve, miniature circuit breaker suitable for Inductive load of following poles in the existing MCB DB complete with connections testing and commissioning etc. as required. (Single pole and neutral)	18	NOS			0.00	INR Zero Only
1.06	Supplying and fixing metal/PVC box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc. as required. 200 mm X 150 mm X 60 mm deep as required.	19	Nos			0.00	INR Zero Only
1.07	Supplying and fixing metal/PVC box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc. as required 200 mm X 250 mm X 60 mm deep as required.	16	Nos			0.00	INR Zero Only
1.08	Supplying & fixing following way, single pole and neutral, sheet steel MCB distribution board, 240V. on surface recess, complete with tinned copper bus bar neutral bus bar, earth bar, din bar, interconnection, powder painted including earthing etc. as required (But without MCB/RCCB/isolator) (2+4 way/6way double door)	7	NOS			0.00	INR Zero Only
1.09	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required. (5/6 Amp Switch)	82	Nos			0.00	INR Zero Only
1.10	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required. 15/16 Amps Switch	23	Nos			0.00	INR Zero Only
1.11	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required.5/6Amps. Socket outlet	37	Nos			0.00	INR Zero Only
1.12	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required. 15/16 Amps Socket	23	Nos			0.00	INR Zero Only
1.13	Supplying and fixing of modular type electronic regulator Supplying & fixing stepped type electronic fan type regulator on the existing modular plate switch box including connection but excluding modular plate etc. as required.	32	Nos			0.00	INR Zero Only
1.14	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 A modular socket outlet and 5/6 A modular switch, connections etc. as required.	28	Nos			0.00	INR Zero Only
1.15	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 Amp modular socket outlet and 15/16 A modular switch, connections etc. as required	12	NOS			0.00	INR Zero Only

1.16	Supplying and fixing following rating, four pole, (single phase and neutral), 415 volts, residual current circuit breaker (RCCB), having a sensitivity current 30 milli amperes in the existing MCB DB complete with connections, testing and commissioning etc. as required. 25 AMP	10	NOS			0.00	INR Zero Only
1.17	Supplying of 3 pin, 5 amps. ceiling rose on existing junction box/ wooden block excluding connection etc. as required	87	NOS			0.00	INR Zero Only
1.18	Supplying and fixing brass batten/ angle holder including connection etc. as required	93	Nos			0.00	INR Zero Only
1.19	Supplying & fixing suitable size GI box with modular plate and cover in front on surface or in recess including providing and fixing 25 A modular socket outlet and 25 A modular SP MCB, "C" curve including connections, painting etc. as required.	3	Nos			0.00	INR Zero Only
1.20	Earthing with G.I. earth plate 600mm x 600mm x 6mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7mtr. long etc. with charcoal/coke and salt as required	3	NOS			0.00	INR Zero Only
1.21	Supplying and laying 6 SWG G.I. wire at 0.50 metre below ground level for conductor earth electrode, including connection/ termination with GI thimble etc. as required. Details of cost for 1 Metres	32	MTR			0.00	INR Zero Only
1.22	Providing and fixing following capacity TP&N disconnecter fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required. For 32 Amp TP&N	7	NOS			0.00	INR Zero Only
1.23	Supplying and fixing of following sizes of medium class PVC conduit/ casking along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required.(20mm dia PVC conduit/ casking)	56	mtr			0.00	INR Zero Only
1.24	Supplying, installing, testing and commissioning of following capacity TPN tap off box made of 1.6mm thick sheet steel enclosure duly painted with powder coating on existing rising mains complete with TPN disconnecter FSU and HRC fuses, connections, earthing etc. as required.100 Amp TPN switch	4	NOS			0.00	INR Zero Only
1.25	Providing of 6 sq mm ttwin core copper cable 1100 Volts grade single phase and neutral.etc as required.	33	MTR			0.00	INR Zero Only
1.26	Providing of fall ceiling panel light 36W and 220V (2 feet x 2 feet)square type for lab and offices	45	Nos			0.00	INR Zero Only
1.27	Providing of surface ceiling light of 18W and 220V (circular type)	32	Nos			0.00	INR Zero Only
1.28	Providing of electric Siren 2 KM range single phase 1/2 HP , 230 Volts for Regional Store Kathara.	1	NOS			0.00	INR Zero Only
1.29	Labour cost of above items no 25,26,27 & 28	1	Job			0.00	INR Zero Only
2	Total impact of GST for the purpose of CTC	1	No.		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					