

| | | | | | | | |
|---|---|---|-----------------------------|-------------------------|--|---|-----------------------|
| Validate | Print | Help | | | | | |
| Tender Inviting Authority: | SO(E&M)/ H | | | | | | |
| Name of the Work / Contract No: | Fresh wiring of quarter no C-04 and B-41, electrical repair work in office building, club and guest house, supply and installation of two nos energy meter at GM unit under Hazaribagh Area | | | | | | |
| Category of Services (To Be Selected by Department) | | Category of Bidder (To Be Selected by Bidder) | To Be Entered by Department | | | | |
| ITC Available | Works Contract | Bidder's Status (Mandatory) | Rate of GST (in %) | Total GST(in Rs.) | GST to be Paid By Bidder (in Rs.) | GST to be Paid By CIL/Subsidiary (in Rs.) | |
| Name of the Bidder/ Bidding Firm / Company : | | Select | 18 | 0.00 | 0.00 | 0.00 | |
| PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) | | | | | | | |
| NUMBER # | TEXT # | NUMBER # | TEXT # | NUMBER | NUMBER # | NUMBER # | TEXT # |
| SL No. | Item Description | Quantity | Units | Estimated Rate in Rs. P | BASIC RATE In Figures To be entered by the Bidder in Rs. P | TOTAL AMOUNT Without Taxes in Rs. P | TOTAL AMOUNT In Words |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| 1 | Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface /recessed PVC conduit, with piano type switch, phenolic laminated sheet, suitable size MS box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group A | 28 | Point | | | 0.00 | INR Zero Only |
| 2 | Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface /recessed PVC conduit, with piano type switch, phenolic laminated sheet, suitable size MS box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group B | 118 | Point | | | 0.00 | INR Zero Only |
| 3 | Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface /recessed PVC conduit, with piano type switch, phenolic laminated sheet, suitable size MS box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C | 16 | Point | | | 0.00 | INR Zero Only |
| 4 | Supplying and fixing PVC batten/ angle holder including connections etc. as required. | 25 | Each | | | 0.00 | INR Zero Only |
| 5 | Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required. 15/16 A socket outlet | 14 | Each | | | 0.00 | INR Zero Only |
| 6 | Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required. 15/16 A switch | 14 | Each | | | 0.00 | INR Zero Only |
| 7 | Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required. 5/6 A socket outlet | 16 | Each | | | 0.00 | INR Zero Only |
| 8 | Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required. 5/6 A switch | 16 | Each | | | 0.00 | INR Zero Only |
| 9 | Supplying and fixing two module stepped type electronic fan regulatoron the existing modular plate switch box including connections but excluding modular plate etc. as required. | 4 | Each | | | 0.00 | INR Zero Only |
| 10 | Supplying and fixing 20 A, 240 V, SPN Industrial type socket outlet, with 2 pole and earth, metal enclosed plug top alongwith 20 A "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required. | 2 | Each | | | 0.00 | INR Zero Only |
| 11 | Supplying and fixing 3 pin, 5 A ceiling rose on the existing junction box/ wooden block including connections etc. as required. | 28 | Each | | | 0.00 | INR Zero Only |
| 12 | Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 6 way, Double door | 2 | Each | | | 0.00 | INR Zero Only |
| 13 | Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.Single pole and neutral | 8 | Each | | | 0.00 | INR Zero Only |
| 14 | Supply and Fixing of 32A Switch Fuse Unit SPN | 3 | Each | | | 0.00 | INR Zero Only |
| 15 | Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire | 262 | Metre | | | 0.00 | INR Zero Only |
| 16 | Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 2 X 4 sq. mm + 1 X 4 sq. mm earth wire | 148 | Metre | | | 0.00 | INR Zero Only |
| 17 | Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required. | 3 | Each | | | 0.00 | INR Zero Only |
| 18 | Providing and fixing 4.00 mm dia copper wire on surface or in recess for loop earthing as required. | 44 | Metre | | | 0.00 | INR Zero Only |
| 19 | Supply and Fixing of Single Phase Energy Meter (10-60A rating) | 1 | Each | | | 0.00 | INR Zero Only |
| 20 | Supply and Fixing of Three Phase Energy Meter (10-60A rating) | 1 | Each | | | 0.00 | INR Zero Only |
| 21 | Providing and fixing of 110Watt flood light | 30 | Each | | | 0.00 | INR Zero Only |
| 22 | Providing of surface downlight 20W S TWIST | 10 | Each | | | 0.00 | INR Zero Only |
| 23 | Providing and fixing of warm white Rope light warm white colour (each roll 45mtr) | 7 | Roll | | | 0.00 | INR Zero Only |
| 24 | Providing of wave light 5Wx2 | 20 | Each | | | 0.00 | INR Zero Only |
| 25 | Providing and fixing of 20watt LED tubelight as required | 75 | Each | | | 0.00 | INR Zero Only |
| 26 | Total impact of GST for the purpose of CTC | 1.00 | Nos | | 0.00 | 0.00 | INR Zero Only |
| Total in Figures | | | | | | 0.00 | INR Zero Only |
| Quoted Rate in Words | | INR Zero Only | | | | | |