

ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Wiring for light point/fan point/exhaust fan point/call bell point with 1.5 sq.mm FR PVC insulated copper Conductorsingle core cable in surface/Recessed PVC conduit, with piano type Switch, phenolic laminated sheet, Suitable size M.S box and earthing the Point with 1.5sqmm. FR PVCInsulated Copper conductor single core cableetc. as required. (Group –"B")	52	Nos			0.00	INR Zero Only
1.02	Wiring for circuit/sub main wiring along with earth wire with the following sizes of PVC insulated copper conductor, single Core cable in surface/recessed PVC Conduit as required(2x1.5sq.mm+ 1.5sq.mm earth wire)	263	Mtr.			0.00	INR Zero Only
1.03	Wiring for circuit/sub main wiring along with earth wire with the following sizes of PVC insulated copper conductor, single Core cable in surface/recessed PVC Conduit as required.2 x 2.5 sq.mm + 1 x 2.5 sq. mm earth wire	139	mtr			0.00	INR Zero Only
1.04	Wiring for circuit/sub main wiring along with earth wire with the following sizes of PVC insulated copper conductor, single Core cable in surface/recessed PVC Conduit as required. 2 x 6 sq.mm + 1 x 6 sq. mm earth wire	97	mtr			0.00	INR Zero Only
1.05	Wiring for circuit/sub main wiring along with earth wire with the following sizes of PVC insulated copper conductor, single Core cable in surface/recessed PVC Conduit as required. 2 x 10 sq.mm + 1 x 10 sq. mm earth wire	44	mtr			0.00	INR Zero Only
1.06	Supplying and fixing following modular switch/Socket on the existing modular plate switch box/cover including connections but excluding modular plate etc. as required. 5/6Amps.switch	38	Nos			0.00	INR Zero Only
1.07	Supplying and fixing following modular switch/Socket on the existing modular plate switch box/cover including connections but excluding modular plate etc. as required. 5/6Amps. Socket outlet	23	Nos			0.00	INR Zero Only
1.08	Supplying and fixing following modular switch/Socket on the existing modular plate switch box/cover including connections but excluding modular plate etc. as required. 15/16 Amps Switch	12	Nos			0.00	INR Zero Only
1.09	Supplying and fixing following modular switch/Socket on the existing modular plate switch box/cover including connections but excluding modular plate etc. as required. 15/16 Amps Socket outlet	12	Nos			0.00	INR Zero Only
1.10	Supplying and fixing of modular type electronic regulator Supplying & fixing stepped type electronic fan type regulator on the existing modular plate switch box including connection but excluding modular plate etc. as required.	26	Nos			0.00	INR Zero Only
1.11	Supplying and fixing metal box of 150mm X 75mm X 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 3 pin 5/6 A socket outlet and 5/6 A piano type switch, connections, painting etc. as required.	15	Nos			0.00	INR Zero Only
1.12	Supplying and fixing metal box of 180mm X 100mm X 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 6 pin 5/6 & 15/16 A socket outletand 15/16 A piano type switch, connections, painting etc. as required.	6	Nos			0.00	INR Zero Only
1.13	Supplying and fixing 3 pin, 5 amp ceiling rose on the existing junction box/ wooden block including connection etc as required.	30	Nos			0.00	INR Zero Only
1.14	Supplyingand fixingPVC batten/ angle holder including connections etc as required.	22	Nos			0.00	INR Zero Only
1.15	Providing and fixing following rating and breaking capacity MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required.(4 pole MCCB, 100A, 30KA)	2	Nos			0.00	INR Zero Only
1.16	Supplying and fixing of following sizes of medium class PVC conduit/ cashing along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required.(20mm dia PVC conduit/ cashing)	67	mtr			0.00	INR Zero Only
1.17	Supplying and laying 6 SWG G.I. wire at 0.50 metre below ground level for conductor earth electrode, including connection/ termination with GI thimble etc. as required. Details of cost for 1 Metres	16	mtr			0.00	INR Zero Only

1.18	Earthing with G.I. earth plate 600mm x 600mm x 6mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7mtr. long etc. with charcoal/coke and salt asrequired.	2	Nos			0.00	INR Zero Only
1.19	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 6 way , Double door	4	Nos			0.00	INR Zero Only
1.20	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MOB DB complete with connections, testing and commissioning etc. as required	16	Nos			0.00	INR Zero Only
1.21	Supplying and fixing following rating, double pole, (single phase and neutral),240 V, residual current circuit breaker (RCCB), having a sensitivity current 30mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.	8	mtr			0.00	INR Zero Only
1.22	Providing of 1.1kv 3 core 6 sq mm copper cable pvc armoured etc. as required	46	mtr			0.00	INR Zero Only
1.23	Providing of change over switch 100Amp, 4 pole 415volts	2	Nos			0.00	INR Zero Only
1.24	Providing of 3 pole main swich fuse unit 415volts 100 amp etc. as required	2	Nos			0.00	INR Zero Only
1.25	Providing of 2.5 sqmm pvc unarmoured cable twin core cpper for park light connection	40	mtr			0.00	INR Zero Only
1.26	Laying of one number additional PVC insulated and PVC sheathed XLPE power cable of 1.1 KV grade of following size direct in ground in the same trench in one tier horizontal formation including excavation and refilling the trench etc as required, but excluding sand cushioning and protective covering.(86 mtr +32 mtr departmental supply 35 sqmm alluminium cable 3 core armured 1.1 kv grade)	118	Mtrs			0.00	INR Zero Only
1.27	Labour charges in SI. No. 23 &24 and other expenses	1	job			0.00	INR Zero Only
2	Total impact of GST for the purpose of CTC	1	No.		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					