

| Validate | | Print | | Help | | Percentage BoQ | |
|--|--|---|--------|-----------------------------|-----------------------|--|---|
| Tender Inviting Authority: Staff Officer(Civil), Magadh-Sanghmitra Area | | | | | | | |
| Name of Work : Providing and Fixing overhead gantry boards at different locations under Magadh OCP of Magadh-Sanghmitra Area. (e NIT No. 41 of 2025-26) | | | | | | | |
| Category of Services (To Be Selected by Department) | | Category of Bidder(To Be Selected by Bidder) | | To Be Entered by Department | | | |
| ITC Available | Works Contract | Bidder's Status (Mandatory) | | Rate of GST (in %) | | GST to be Paid By Bidder (in Rs.) | GST to be Paid By CIL/Subsidiary (in Rs.) |
| Name of the Bidder/ Bidding Firm / Company : | | Select | | 18.00 | | 0.00 | 0.00 |
| PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) | | | | | | | |
| NUMBER # | TEXT # | NUMBER # | TEXT # | NUMBER | NUMBER # | TEXT # | |
| Sl. No. | Item Description | Quantity | Units | Estimated Rate in Rs. P | TOTAL AMOUNT in Rs. P | TOTAL AMOUNT In Words | |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | |
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed. | 125.11 | cum | 128.05 | 16020.34 | INR Sixteen Thousand &Twenty and Paise Thirty Four Only | |
| 2 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size derived from natural sources) | 7.14 | cum | 5524.65 | 39446.00 | INR Thirty Nine Thousand Four Hundred & Forty Six Only | |
| 3 | Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size) | 31.93 | cum | 7365.50 | 235180.42 | INR Two Lakh Thirty Five Thousand One Hundred & Eighty and Paise Forty Two Only | |
| 4 | Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars | 4789.50 | kg | 75.85 | 363283.58 | INR Three Lakh Sixty Three Thousand Two Hundred & Eighty Three and Paise Fifty Seven Only | |
| 5 | Centring and shuttering including strutting, propping etc. and removal of form for removal of form for: Foundations, footings, bases of columns etc. for mass concrete. | 79.20 | sqm | 262.55 | 20793.96 | INR Twenty Thousand Seven Hundred & Ninety Three and Paise Ninety Six Only | |
| 6 | Providing and fixing mild steel round holding down bolts with nuts and washer plates complete. | 888.45 | kg | 75.35 | 66944.71 | INR Sixty Six Thousand Nine Hundred & Forty Four and Paise Seventy One Only | |
| 7 | Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. | 14023.72 | kg | 92.55 | 1297895.29 | INR Twelve Lakh Ninety Seven Thousand Eight Hundred & Ninety Five and Paise Twenty Nine Only | |
| 8 | Manufacturing, supplying and fixing retro reflective overhead signage boards made up of 2 mm thick aluminium sheet, face to be fully covered with high intensity and encapsulated lens type heat activated retro reflective sheeting conforming to type - III of ASTM-D-4956-01 as approved by Engineer-in-charge, letters, borders etc. as per IRC : 67-2001 in silver white with blue colour back ground and with high intensity grade, pasted on substrate by pressure sensitive adhesive backing which shall be activated by applying pressure conforming to class II of ASTM-D-4956-01 and fixing the same to the plate of structural frame work by means of suitable sized aluminium alloys, rivets or bolts & nuts @ 300 mm centre to centre all along the periphery as well as in two vertical rows along with theft resistant measures, including the cost of painting with two or more coats of epoxy paint in grey colour on the back side of aluminium sheet including appropriate priming coat. The rate includes the cost of rounding off the corners, lowering down the structural frame work from the gantry, fixing and erecting the same in position all complete as per drawings, specification and direction of the engineer-in-charge.(Structural frame work including M.S. plate to be provided separately. Rectangular area of the sheet only shall be measured for payment). Overhead informatory road signage | 200.16 | sqm | 4849.00 | 970575.84 | INR Nine Lakh Seventy Thousand Five Hundred & Seventy Five and Paise Eighty Four Only | |

| | | | | | | |
|------------------------|--|--------|--------|-------|------------|--|
| 9 | Painting with synthetic enamel paint : Two or more coats on new work | 400.00 | sqm | 99.90 | 39960.00 | INR Thirty Nine Thousand Nine Hundred & Sixty Only |
| 10 | Total impact of GST for the purpose of CTC | 1.000 | Nos | 0.00 | 0.00 | INR Zero Only |
| Total in Figures | | | | | 3050100.12 | INR Thirty Lakh Fifty Thousand One Hundred and Paise Twelve Only |
| Quoted Rate in Figures | | | Select | | 0.00 | INR Zero Only |
| Quoted Rate in Words | | | | | | INR Zero Only |