

Tender Inviting Authority: Project Engineer(E&M), Bhurkunda Colliery, Barka-Sayal Area, CCL.

Name of the Work / Contract No:		Supply and fixing of change over switch 100Amp/415V/ 50Hz (four pole) (02Nos), 200Amp/415V/50Hz, (four pole) (02 Nos) for different location and fabrication of 01 No Shade with chemical earth pit for DG Set at Rest house Bhurkunda Project.		NIT No. : PE(EnM)/BHK/e Tender/25-26/28      Dated: 08/10/2025		
Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected)				
ITC Not Available	Works Contract	Bidder's Status (Mandatory)		Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select		0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	12	6	7	8
1	Supply and fixing of changeover switch (Four Pole of load). 200Amp/415V/50Hz	2.00	Nos.	INR		0.00	INR Zero Only
2	Supply and fixing of changeover switch (Four Pole on load). 100Amp/415V/50Hz	4.00	Nos.	INR		0.00	INR Zero Only
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	699.15	Kg	INR		0.00	INR Zero Only
4	With 3 meter GI Pipes having outer pipe dia of 50mm having 80-200 micron galvanizing Inner pipe dia of 25mm having 200-250 micron galvanizing connection terminal dia of 12mm in nominal soil with 50 kg (tow bag) back filling bentonite compound U/L listed and confirm to relevant International/Indian standards around electrode upto ground level.	2.00	Nos.	INR		0.00	INR Zero Only
5	Filling available excavated earth (excluding rock) in trenches, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 metres.	6.00	Cum	INR		0.00	INR Zero Only
6	Excavation for cable trenches in soft soil, depth up to 1.2 m including dressing of sides lift up to 1.5 m, including getting out the excavated soil, refilling with sand and or good soil after laying of cable/ pipe etc in layers of 20 cm, ramming, watering and disposal of surplus excavated soil as directed, within a lead of 50 metres.	6.00	Cum	INR		0.00	INR Zero Only
7	Total impact of GST for the purpose of CTC	1.000	Nos	INR	0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					