

Print	

Item Rate BoQ

Tender Inviting Authority : Staff Officer (Civil), Amrapali-Chandragupta Area.

Name of Work: Repairing of approach road near Coal Stock 49 under Amrapali OCP of A-C Area. CCL. (eNIT No. 34 of 2025-26)

Name of Work: Repa	ring of approach road near Coal Stock 49 under Amrapali OCP of A-C Area, CCL. (eNIT No. 34 o	f 2025-26)						
	Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract		Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :			Select	18	0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)								
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #	
SI. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words	
1	2	3	4	5	6	7	8	
1	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kind of soil.	1483.2	cum			0.00	INR Zero Only	
2	Removal of Unserviceable Soll with Disposal upto 1000 metres (Removal of unserviceable soil including excavation, loading and disposal upto 1000 metres lead but excluding replacement by suitable soil which shall be paid separately as per clause 305.)	633.82	cum			0.00	INR Zero Only	
3	Construction of sub-grade and earthen shoulders with approved material obtained from borrow pits with all lifts & leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of table No. 300-2.Rolling with vibrátory roller.	4480	cum			0.00	INR Zero Only	
4	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only	
Total in Figures							INR Zero Only	
Quoted Rate in Word	INR Zero Only			l				