Bill of quantity for the work Provision of platform and fence around Transformer near AITUC Office (Sri Ramendra Kumar) at Sayal-D project (BS).

	Description				
S. N.		Qnty	Unit	Updated Rate	Updated Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	51.22	cum	188.45	9652.41
2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	4.16	sqm	5322.15	22140.14
3	12mm cement plaster of mix: 1:6 (1cement : 6fine sand).	18.00	sqm	217.70	3918.6
4	Cement concrete flooring 1:2:4 (1cement : 2coarse sand : 4graded stone aggregates) finished with a floating coat of neat cement including cement slurry but excluding the cost of nosing of steps etc. complete: 40 mm thick with 20 mm nominal size stone aggregates.	20.25	sqm	452.50	9163.13
5	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	144.40	kg	77.95	11255.98
6	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50mm (base metal of minimum 0.45mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	45.00	sqm	571.00	25695
7	Extra for providing and fixing wind ties of 40x 6 mm flat iron section.	45.00	metre	138.75	6243.75
		Total Rs.		88069.01	
		Add GST @18%		15852.42	
<u></u>		Total Amount			103921.43