

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Staff officer (E&amp;M), NK Area, CCL

Name of the Work / Contract No:	Providing and Installation of Lightening Arrestor and construction of earth pits with required accessories at Weighbridges in respect of Churi Colliery, NK Area	NIT No. GM (NK)/EnM/eNIT/2025-26/97; dated 09.10.2025.			
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc as required. Above 10.00 Metre and upto 12.00 Metre.	4.00	Nos		0.00	INR Zero Only
2	Providing and fixing 25 mm x 5 mm GI strip on surface or in recess for connections as required.	60.00	Mtr		0.00	INR Zero Only
3	Providing and fixing 4.00 mm dia copper wire on surface or in recess for loop earthing as required.	150.00	Mtr		0.00	INR Zero Only
4	Providing and fixing 25 mm x 5 mm copper strip on surface or in recess for connections as required.	25.00	Mtr		0.00	INR Zero Only

5	Earthing with copper earth plate 600mm x 600mm x 3mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/ coke and salt as required.	8.00	Nos		0.00	INR Zero Only
6	Providing and making steel pole collar with cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm) of specified size and shape including form work, plastering if required, curing etc as required ( 8 x 0.30 cum = 2.40 cum)	2.40	Cum		0.00	INR Zero Only
7	Providing of Lightning arrestor	8.00	Nos		0.00	INR Zero Only
8	Providing of elappy epoxy electrical insulator with nut, bolt and washer	32.00	Nos		0.00	INR Zero Only
9	Labour cost on Item No. 7 and 8	1.00	job		0.00	INR Zero Only
10	Pole painting two coats (Aluminium Paint)	8.00	Nos		0.00	INR Zero Only
11	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	0.00	0.00	INR Zero Only
<b>Total in Figures</b>					0.00	INR Zero Only
<b>Quoted Rate in Words</b>		<b>INR Zero Only</b>				