

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL

Name of the Work / Contract No:	Providing and fixing of service cable connection, lightening arrestor and earth pits for 01 Nos. Multistory B type block and 03 Nos. C type Multistory block at Subhash Nagar Colony under KDH Project, NK Area	NIT No. GM (NK)/EnM/eNIT/2025-26/98; dated 09.10.2025.			
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Wiring for circuit / submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required 4 x 16 sq. mm + 2 x 6 sq. mm earth wire.	260.00	Mtr		0.00	INR Zero Only
2	Providing and fixing of lighening arrestor	5.00	Nos		0.00	INR Zero Only
3	Wiring for circuit / submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required 2 x 4 sq. mm + 1 x 4 sq. mm earth wire.	200.00	Mtr		0.00	INR Zero Only
4	Providing and fixing 50 mm x 5 mm GI strip on surface or in recess for loop earthing as required.	230.00	Mtr		0.00	INR Zero Only

5	Providing and fixing of insulated PVC sleeve for 50 mm x 5 mm G.I. strip	230.00	Mtr		0.00	INR Zero Only
6	Providing and fixing of PVC stopper	46.00	Nos		0.00	INR Zero Only
7	Earthing with copper earth plate 600mm x 600mm x 3mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/ coke and salt as required.	9.00	Nos		0.00	INR Zero Only
8	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				