

Tender Inviting Authority:	Project Engineer (EnM), KOCP, Hazaribagh Area					
Name of the Work / Contract No:	Erection of 3.3KV OH line at IV seam and improving illumination at Coal stock, pumping site and Haul road at KOCP under Hazaribagh Area.					
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Erection of steel tubular or rail pole strut in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling and secured with holding clamps, bolts, nuts, etc. as required.	6	Nos.			0.00	INR Zero Only
2	Erection of pole top/ straight two wire/ V shape two wire, angle iron/ channel	6	Set			0.00	INR Zero Only
3	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above including binding etc. as required.	224.7	Kg			0.00	INR Zero Only
4	Dismantling of pole/ street light standard/ strut embedded in cement concrete foundation etc. as required	2	Nos.			0.00	INR Zero Only
5	Dismantling of over head lines comprising of copper/ aluminium over head conductor, GI wire, cross arms, insulators etc. as required.	224.7	Kg			0.00	INR Zero Only
6	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for two 11 KV over head line conductors complete with 50 mm X 50 mm X 6 mm (angle iron bracket welded to the channel iron and complete with 50 mm X 6mm M.S. flat iron clamps, bolts and nuts including drilling holes for insulator pins, bolts, nuts and washers etc (as per drawing) and painting with primer and finish paint as required.	6	Nos.			0.00	INR Zero Only
7	Erection of angle iron/ channel iron cross arm on wood/ RCC/ PCC/ steel tubular / rail pole etc. as required	6	Set			0.00	INR Zero Only
8	Supplying and erection of 11 KV pin insulator complete with large steel head G.I. pin, nuts, washers etc. as required.	6	Nos.			0.00	INR Zero Only
9	Supplying and erection of 11 KV disc insulator for 11 KV over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required.	6	Nos.			0.00	INR Zero Only
10	Supplying and erection of 100 mm X 110 mm shackle insulator with G. I. Bolt, nuts and straps etc. as required .	6	Nos.			0.00	INR Zero Only
11	Supplying and erection of 100 mm X 80 mm pin insulator complete with G.I. Spindle and nuts etc. as required .	6	Nos.			0.00	INR Zero Only
12	Supplying and erection of galvanised stay set for 11 KV over head lines complete with 19/ 20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm thick, thimble, stay clamps, turn buckle (20 mm X 600 mm), 7/ 4.00 mm dia G.I. stay wire and 11 KV strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	4	Nos.			0.00	INR Zero Only
13	Supply and fixing of 200W LED light with holder and wire for connection	50	Nos.			0.00	INR Zero Only
14	Total impact of GST for the purpose of CTC	1.00	No		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						