Validate	Print Help Percentage BoQ						
Tender Inviting Authority:STAFF OFFICER CIVIL							
Name of Work: Annual maintenance contract for day-to-day cleaning and maintenance of WBs (03nos.), Check Post and ETP at under Tapin North OCP, Hazaribagh Area for 02 years							
	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)		
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00		
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name							

and Values only)

NUMBER# TEXT # NUMBER# TEXT# NUMBER NUMBER# TEXT# SI. Item Description Quantity Units Estimated Rate in TOTAL AMOUNT in TOTAL AMOUNT in Words No. Rs. P Rs. P 2 3 4 5 6 Item Description/ Heading Upkeeping of weighbridges by engadging two unskilled labour per day for each weighbridge including daily brooming and weekly mopping of floor in the control room, cleaning of glass panes/wooden panels of window/door shutters, furniture, window grills etc of 1392314.40 INR Thirteen Lakh Ninety Two Thousand Three Hundred & Fourteen and Paise Forty Only control room, cleaning of weighing platform, load cell its support 1.01 2190.00 Nos. 635.76 structure, apporach to the platform, spillage coal from under the platform etc as per the direction of Engineer-in-charge including the cost of al consumables like brooms, detergents, phenyle etc. (One labour to be deployed per one unit of WB as per the instruction of Cleaning, mopping & washing of public buildings & other places neatly with detergent bleaching power etc. all complete with tools, 1.02 13140.00 0.65 8541.00 INR Eight Thousand Five Hundred & Forty One Only Sqm tackles and consumables to make the floor clean & hygeinic as per the instruction of the EIC Distempering with 1st quality acrylic distemper (ready mixed) having VOC (Volatile Organic Compound) content less than 50 gram/litre, of 1.03 480.00 Sqm 38.55 18504.00 INR Eighteen Thousand Five Hundred & Four Only apporved brand and of required said and colour complete to give and even shade. Old work (one or more coats) Providing and applying white cement based putty of average 23628.00 INR Twenty Three Thousand Six Hundred & Twenty Eight Only thickness 1 mm, of approved brand and manufacturer, over the 1.04 240.00 98.45 Sqm plastered wall surface to prepare the surface even and smooth complete.

1.05	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats @ 2.20 kg/10 sqm) complete.	480.00	Sqm	48.35	23208.00	INR Twenty Three Thousand Two Hundred & Eight Only
1.06	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	100.00	Sqm	195.85	19585.00	INR Nineteen Thousand Five Hundred & Eighty Five Only
1.07	12 mm cement plaster of mix : 1:6 (1 cement : 6 fine sand)	120.00	Sqm	217.70	26124.00	INR Twenty Six Thousand One Hundred & Twenty Four Only
1.08	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 cement: 4 find sand)	400.00	Sqm	284.75	113900.00	INR One Lakh Thirteen Thousand Nine Hundred Only
1.09	Brick work with common burnt clay F.P.S. (non modualr) bricks of class designation 7.5 in foundation and plinth in : Cement mortar 1:6 (1 cement : 6 coarse sand)	10.00	Cum	5322.15	53221.50	INR Fifty Three Thousand Two Hundred & Twenty One and Paise Fifty Only
1.10	Providing and laying in position cement of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size)	5.00	Cum	6490.90	32454.50	INR Thirty Two Thousand Four Hundred & Fifty Four and Paise Fifty Only
1.11	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of apporved steel primer all comlete	200.00	Кg	92.55	18510.00	INR Eighteen Thousand Five Hundred & Ten Only
1.12	Welding by gas or electric plant including transporatation of plant at site etc. complete	6000.00	cm	2.95	17700.00	INR Seventeen Thousand Seven Hundred Only
1.13	Painting with synthetic enamel paint of apporved brand and maufacture to give an even shade : Two or more coats on new work	500.00	Sqm	99.90	49950.00	INR Forty Nine Thousand Nine Hundred & Fifty Only
1.14	Lettering with black Japan paint of approved brand and manufacture	10000.00	units	3.70	37000.00	INR Thirty Seven Thousand Only
1.15	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level: 1:1.5:3 (1 cement: 1.5 coarse sand: 3 graded stone aggregate 20 mm nominal size)	2.00	Cum	7365.50	14731.00	INR Fourteen Thousand Seven Hundred & Thirty One Only
1.16	Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in postion and binding all complete up to plinth level. Thermo-Mechnically Treated bars.	160.00	к	75.85	12136.00	INR Twelve Thousand One Hundred & Thirty Six Only
1.17	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS:733 and IS:1285, fixing with dash fasterners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Alumimium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, ALuminium snap beading for glazing / paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately): For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS:1868, Minimum anodic coating of grade AC 15)	15.00	Кg	367.10	5506.50	INR Five Thousand Five Hundred & Six and Paise Fifty Only
1.18	Anodised aluminium (anodised transparent or dyed to required shade according to IS:1868, Minimum anodic coating of grade AC 15)	15.00	Kg	434.00	6510.00	INR Six Thousand Five Hundred & Ten Only

Quoted Rate in Words			INR Zero Only					
Quoted Rate in Figures			Select		0.00	INR Zero Only		
Total in Figures						INR Twenty Three Lakh Fifty Five Thousand Two Hundred & Forty Nine and Paise Ninety Three Only		
2.00	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only		
1.22	Clearing jungle including uprooting of rank vegetation, grass, brush wood trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	8000.00	Sqm	10.20	81600.00	INR Eighty One Thousand Six Hundred Only		
1.21	Carriage of earth by mechanical transport including loading and stacking lead 5 K.M.	1086.30	Cu.m.	210.10	228231.63	INR Two Lakh Twenty Eight Thousand Two Hundred & Thirty One and Paise Sixty Three Only		
1.20	Earth work in excavation by mechanical means (Hydraulic excavator)/ Manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5, disposal earth to be levelled and neatly dressed. All kinds of soil	1278.00	Cum	128.05	163647.90	INR One Lakh Sixty Three Thousand Six Hundred & Forty Seven and Paise Ninety Only		
1.19	Providing and fixing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber/ neoprene gasket etc. complete as per the architectural drawings and the directions fo engineer-incharge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 4.0 mm thickness	10.00	Sqm	824.65	8246.50	INR Eight Thousand Two Hundred & Forty Six and Paise Fifty Only		