

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Project Engineer(EnM),Sayal-D Project, Barka-Sayal Area, CCL.

Name of the Work / Contract No:	Dismantling, shifting, installation,commissioning, Testing & calibration of one no. of 50MT capacity electronic weighbridge ASEC make from KK More to new proposed site required spares of Sayal-D Project.				
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Supply & fixing Mounting Assembly	4.00	Set		0.00	INR Zero Only
2	Supply & fixing of insulating Pad	8.00	Nos		0.00	INR Zero Only
3	Supply & fixing complete set of bolts with nuts	1.00	LS		0.00	INR Zero Only
4	Supply & fixing foundation Nolts	16.00	Nos		0.00	INR Zero Only
5	Supply & fixing Base Plate (350 mm X 600 mm X 25 mm)	4.00	Nos		0.00	INR Zero Only
6	Supply & fixing Stopes & Burnps	4.00	Set		0.00	INR Zero Only
7	Dismatling of 50MT road weighbridge	1.00	LS		0.00	INR Zero Only
8	Conduiting of all loadcell cable up to junction Box	1.00	Job		0.00	INR Zero Only
9	Erection commissioning fixing & aligement of weighbridge	1.00	Job		0.00	INR Zero Only
10	Testing calibration etc.	1.00	job		0.00	INR Zero Only
11	Cleaning testing & Adjusting of CI test weights for stamping	1,250.00	Nos		0.00	INR Zero Only
12	Contractor Profit	1.00	Nos		0.00	INR Zero Only
13	Earthworkinexcavationbymechnicalmeans(Hydraulicexcavator)/manual ansin foundation trenches or drains (notexceeding 1.5min widt hor10 sqmonplan) ,including dressing of side sand ramming of bottoms,foralllift, in cluding getting out the excavated soiland disposal of surplus excavated soil as directed, within a lead of 50 m.	46.69	cum		0.00	INR Zero Only

14	Filling available excavated earth (excluding rock) in trenches, plinth. Sides of foundation setc. In layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50m and for all lift	4.50	cum		0.00	INR Zero Only
15	supplying and filling in plinth with jamuna sand under floors including watering ramming consolidation and dressing complete	3.11	cum		0.00	INR Zero Only
16	Providing and laying cement concrete of specified grade excluding the cost of centering and shuttering in all works up to plinth level 1:4:8 (1cement : 4 fine sand : 8graded stone aggregates 40 mm nominal size)	1.73	cum		0.00	INR Zero Only
17	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering ,shuttering ,finishing and rein for cement-All work up to plinth level :1:1:5:3(1cement :1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	10.28	cum		0.00	INR Zero Only
18	SteelreinforcementforR.C.C.workincludingstraightening,cutting ,bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars	916.80	kg		0.00	INR Zero Only
19	Providingandlayinginpositioncementconcreteofspecifiedgrade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4(1cement: 2 coarse sand : 4graded stone aggregate 20 mm nominal size)	4.50	cum		0.00	INR Zero Only
20	Centering and shuttering including strutting propping etc. and removal of from for: Foundations, footings bases of columns, etc for mass concrete.	21.49	sqm		0.00	INR Zero Only
21	Total impact of GST for the purpose of CTC	1.000	No.	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				