

Item Rate BoQ

Tender Inviting Authority: Project Engineer (E&M), Ashok OCP, Piparwar Area							
Name of the Work / Contract No:	Work of repairing of damaged electrical wiring of weigh bridge no. 1,5,7,8,12,13 &14 at different location under Ashok OCP, Piparwar Area.				NIT No. : PO(AK)/PE/(EnM)/e-NIT/25-26/35		
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)		Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate (With taxes) in Rs. P	BASIC RATE (Without taxes) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Point wiring in PVC conduit,with piano type switch: wiring for light point/fan point/exhaust fan point/call bell with 1.5sqmm FRLS PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit,with piano type switch,phenolic laminayed sheet,suitable size M.S. box and earthing the point with 1.5sqmm FRLS PVC insiated copper conductor single core cable etc as required.	110	Nos	933.38		0.00	INR Zero Only
2	Power plug wiring In PVC conduit (2x2.5sqmm) wiring for circuit/submain along with earth wire with 1x1.5sqmm sizes of FRLS PVC insulated copper conductor ,single core cable in surface/recessed medium class PVC conduit as required.	125	Mtr	267.86		0.00	INR Zero Only
3	Wiring for light/power plug with 2X4sq. Mm FRLS PVC insulated copper conductor single core cable in surface/ recessed medium calss.PV Conduit along with 1 Nos 4 sq. Mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	128	Mtr	329.22		0.00	INR Zero Only
4	Supplying and fixing stepped type electronic fan regulator on the existing modular plate switch box including connection but excluding modular plate etc as required.	11	Nos	369.34		0.00	INR Zero Only
5	Supplying and fixing DP sheet steel enclosure on surface/ reces along with 5 25/32 A 240 V "C" curve DP MCB complete with connections, testing and commissioning etc. as required.	7	Nos	1180.00		0.00	INR Zero Only
6	Supplying and fixing Single pole 5 amps to 32 amps rating, 240 volts, "C" curve, 6 miniature circuit breaker in the existing MCB DB complete with connections & 8 testing etc. as required.	8	Nos	253.70		0.00	INR Zero Only
7	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of single poles and neutral in the existing MCB DB complete with connections, testing and commissioning etc, as required.	7	Nos	607.70		0.00	INR Zero Only
8	Supplying and fixing 15/16amp switch.	25	Nos	116.82		0.00	INR Zero Only
9	Supplying and fixing 6 pin 15/16 A socket outlet	25	Nos	133.34		0.00	INR Zero Only
10	Supply of 36w tubelight fitting	18	Nos	400.00		0.00	INR Zero Only
11	For service connection: Supplying and drawing 2x6sqmm sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/PVC conduit as required.	290	Mtr	217.12		0.00	INR Zero Only
12	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						