

Tender Inviting Authority:	SO (EnM)					
Name of the Work / Contract No:	Day to day maintenance of existing 6" dia pipeline with pump shifting/pipe shifting from main quarry to Parej filter plant for the period of one year of PEOCP under Hazaribag Area.					
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder In Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Dismantale of 150mm dia M.S/G.I pipe of gradient less then 45 degrees	150	Mtr			0.00	INR Zero Only
2	Laying of 150mm dia M.S/G.I pipe of gradient less then 45 degrees	150	Mtr			0.00	INR Zero Only
3	Supply & fixing of M.S flange 150mm dia	60	No's			0.00	INR Zero Only
4	Supplying Bolts and nuts 20 mm dia 75 mm long	100	No's			0.00	INR Zero Only
5	Supply and fixing of Non-return valve for 150mm dia pipe(Heavy duty)	3	No's			0.00	INR Zero Only
6	Supply and fixing of sluice valve for 150mm dia pipe(Heavy duty)	3	No's			0.00	INR Zero Only
7	Supply and fixing of Foot valve for 150mm dia pipe(Heavy duty)	1	No's			0.00	INR Zero Only
8	Welding work for water leakage/damage of existing pipeline	5000	cm			0.00	INR Zero Only
9	Dismantling, Shifting and Installation of 01 nos 1000 GPM Pump set with base frame, suction pipeline, valves etc.	6	Times			0.00	INR Zero Only
10	Excavation for cable trenches in soft soil, depth upto 1.2 m including dressing of sides lift upto 1.5 m, including getting out the excavated soil, refilling with sand and or good soil after laying of cable/ pipe etc in layers of 20 cm, ramming, watering and disposal of surplus excavated soil as directed, within a lead of 50 metres.	275	cum			0.00	INR Zero Only
11	Total impact of GST for the purpose of CTC	1.00	No		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					