

Validate

Print

Help

**Item Rate BoQ**

Tender Inviting Authority: Project Engineer(EnM),Sayal-D Project, Barka-Sayal Area, CCL.

|                                              |                                                                                                                                                                                                                                                                                        |                                               |                   |                                   |                                           |
|----------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------|-------------------|-----------------------------------|-------------------------------------------|
| Name of the Work / Contract No:              | Erection and dismantling of HT pole and conductor on as and when required basis for a period of one year (365 days) in Sayal-D HT O.H. line maintenance (Sayal main 11kV feeder from Urimari 33/11kV S/s, 3.3kV line of Jamuria, KKC, Nalapar and Sayal-D OCP ) under Sayal-D Project. |                                               |                   |                                   |                                           |
| .                                            | Category of Services (To Be Selected by Department)                                                                                                                                                                                                                                    | Category of Bidder (To Be Selected by Bidder) |                   |                                   |                                           |
| ITC Not Available                            | Works Contract                                                                                                                                                                                                                                                                         | Bidder's Status (Mandatory)                   | Total GST(in Rs.) | GST to be Paid By Bidder (in Rs.) | GST to be Paid By CIL/Subsidiary (in Rs.) |
| Name of the Bidder/ Bidding Firm / Company : |                                                                                                                                                                                                                                                                                        | Select                                        | 0.00              | 0.00                              | 0.00                                      |

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

| NUMBER # | TEXT #                                                                                                                                                                                                                                                                                                                                                                                                                 | NUMBER # | TEXT # | NUMBER #                                                   | NUMBER #                            | TEXT #                |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|--------|------------------------------------------------------------|-------------------------------------|-----------------------|
| Sl. No.  | Item Description                                                                                                                                                                                                                                                                                                                                                                                                       | Quantity | Units  | BASIC RATE In Figures To be entered by the Bidder in Rs. P | TOTAL AMOUNT Without Taxes in Rs. P | TOTAL AMOUNT In Words |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                      | 3        | 4      | 6                                                          | 7                                   | 8                     |
| 1        | Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required Above 08.00 metre and upto 10.00 metre                                                                                                                                                                  | 20       | Each   |                                                            | 0.00                                | INR Zero Only         |
| 2        | Supplying and erection of stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod , anchor plate of size 45 cm X 45cm X 7.5mm, thimble, stay clamps , turn buckle (20mmX60cm), 7/3.15 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1cement:3 coarse sand: 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required. | 3546     | kg     |                                                            | 0.00                                | INR Zero Only         |

|    |                                                                                                                                                                                                                                                                                                                                                                                                                                                               |        |      |  |      |               |
|----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|--|------|---------------|
| 3  | Supplying of channel iron 75mm X 40mm X 6mm (7.14 kg per metre) cross arm for 2 wire overhead line complete with clamps, bolts,nuts and washer etc including drilling of holes for insulator pin setc (as per drawing) and painting with primer and finished paint as required.                                                                                                                                                                               | 10     | Set  |  | 0.00 | INR Zero Only |
| 4  | Supplying of channel iron 75mm X 40mm X 6mm (7.14 kg per metre) cross arm for 4 wire overhead line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pin setc (as per drawing) and painting with primer and finished paint as required.                                                                                                                                                                              | 10     | Each |  | 0.00 | INR Zero Only |
| 5  | Erection of angle iron / channel iron cross arm on wood / RCC/ PCC/ steel tubular / rail pole etc. as required.                                                                                                                                                                                                                                                                                                                                               | 10     | Each |  | 0.00 | INR Zero Only |
| 6  | Supplying and erection of a set of cross bracing FRLS ame work for 11 KV over head line double pole structure having four members fabricated out of 50 mm X 50 mm X 6mm angle iron to form a rectangle of minimum size 1400 mm width X 2500 mm height, complete with 50 mm X6mm M.S. flat iron clamps, bolts and nuts including drilling holes for insulator pins, bolt sand nuts etc (as per drawing) and painting with primer and finish paint as required. | 30     | Set  |  | 0.00 | INR Zero Only |
| 7  | Supply of G.I wire 8 SWG including binding etc.                                                                                                                                                                                                                                                                                                                                                                                                               | 2      | Set  |  | 0.00 | INR Zero Only |
| 8  | Erection of G.I wire No. 8 SWG including binding etc. as required.                                                                                                                                                                                                                                                                                                                                                                                            | 4      | Each |  | 0.00 | INR Zero Only |
| 9  | Erection of cradle as reqd. (03 nos)                                                                                                                                                                                                                                                                                                                                                                                                                          | 2      | Set  |  | 0.00 | INR Zero Only |
| 10 | Supplying and erection of 75 mm x 90 mm shackle insulator with G I bolt, nut and as required.                                                                                                                                                                                                                                                                                                                                                                 | 30     | Set  |  | 0.00 | INR Zero Only |
| 11 | Supplying and erection of 100 mm x 65 mm Pin insulator with GI bolt and nuts etc as required.                                                                                                                                                                                                                                                                                                                                                                 | 30     | set  |  | 0.00 | INR Zero Only |
| 12 | Erection of all aluminium conductor of 7/1.96mm to 7/3.10mm diameter including binding etc as required. (0.4KM x 5-wire) x 171kg/Km= 342.00 kg)                                                                                                                                                                                                                                                                                                               | 50     | Set  |  | 0.00 | INR Zero Only |
| 13 | Dismantling of Pole/ street light standard /strut embedded in cement concrete foundation etc as reqd.                                                                                                                                                                                                                                                                                                                                                         | 10     | Set  |  | 0.00 | INR Zero Only |
| 14 | Dismantling of over head line comprising of cooper/ aluminium over head condutor G.I wire cross arms, insulators etc as reqd.                                                                                                                                                                                                                                                                                                                                 | 10     | Set  |  | 0.00 | INR Zero Only |
| 15 | loading Transporting and unloading of Poles and OH materials from store to working site.                                                                                                                                                                                                                                                                                                                                                                      | 317.76 | kg   |  | 0.00 | INR Zero Only |
| 16 | providing and fixing M.V danger notice plate of 200 mm x 150 mm, made of mild steel, at least 2 mm thick, and vitreous enameled white on both sides, and wth inscription in single red colour on frount side as reqd.                                                                                                                                                                                                                                         | 317.76 | kg   |  | 0.00 | INR Zero Only |

|                             |                                                                                                                                                               |                      |          |             |             |               |
|-----------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|----------|-------------|-------------|---------------|
| 17                          | Analyzed rate for supply, installation and laying of aluminium cable<br>10 sq mm 2 core 1.1KV grade IS 7098 suitable for use in mines<br>(Service connection) | 10                   | Each     |             | 0.00        | INR Zero Only |
| 18                          | Analyzed rate for supply, installation and laying of aluminium cable<br>10 sq mm 2 core 1.1KV grade IS 7098 suitable for use in mines<br>(Service connection) | 730                  | Nos      |             | 0.00        | INR Zero Only |
| 19                          | Analyzed rate for supply, installation and laying of aluminium cable<br>10 sq mm 2 core 1.1KV grade IS 7098 suitable for use in mines<br>(Service connection) | 10                   | Each     |             | 0.00        | INR Zero Only |
| 20                          | Analyzed rate for supply, installation and laying of aluminium cable<br>10 sq mm 2 core 1.1KV grade IS 7098 suitable for use in mines<br>(Service connection) | 3546                 | kg       |             | 0.00        | INR Zero Only |
| 21                          | Analyzed rate for supply, installation and laying of aluminium cable<br>10 sq mm 2 core 1.1KV grade IS 7098 suitable for use in mines<br>(Service connection) | 200                  | per Tree |             | 0.00        | INR Zero Only |
| 22                          | Analyzed rate for supply, installation and laying of aluminium cable<br>10 sq mm 2 core 1.1KV grade IS 7098 suitable for use in mines<br>(Service connection) | 20                   | Per Pole |             | 0.00        | INR Zero Only |
| 23                          | <b>Total impact of GST for the purpose of CTC</b>                                                                                                             | 1.000                | No.      | <b>0.00</b> | 0.00        | INR Zero Only |
| Total in Figures            |                                                                                                                                                               |                      |          |             | <b>0.00</b> | INR Zero Only |
| <b>Quoted Rate in Words</b> |                                                                                                                                                               | <b>INR Zero Only</b> |          |             |             |               |