Help

Item Rate BoQ

valuate rink nep item rate box							
Tender Inviting Authority: Project Engineer(E&M), Bhurkunda Colliery, Barka-Sayal Area, CCL.							
Name of the Work / Contract No:	Rearrangement of 11KV OH Line and extension of 440V, 35sqi Colony and Hospital Colony respectively for smooth operatio Colliery.	under Bhurkunda NIT No. : PE(EnM)/			HK/e Tender/25-26/30 Dated: 01/11/2025		
	Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)	•			
ITC Not Available	Works Contract		Bidder's Status (Mandatory)		Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select		0.00	0.00	0.00
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT#	TEXT #	NUMBER #	NUMBER #	TEXT #
SI. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement: 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required. Above 10.00 metre and upto 12.00 metre	3.00	No.	INR	6		INR Zero Only
	Erection of all aluminium conductor of 71/196 mm to 7/3.10 mm diameter including binding etc. as required. 2 SPAN X 50 MrsxX 3 wire X 342.51 Kg/KM=102.75 KG Total = 103 KG (say)	103.00	Kg	INR		0.00	INR Zero Only
	Supplying and erection of galvanised stay set for 11 KV over head lines complete with 19½ 0 mm dia X1.8 metres long stay rod, anchor plate of size 45 cm X4.5 cm X7.5 mm thick, thimble, stay clamps, turn buckle (20 mm X, 600 mm), 74.400 mm dia G1. stay wire and 11 KV strain insulator et in enement concrete 13.56 (1 erement 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	3.00	Set	INR			INR Zero Only
4	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) pole top bracket/ cross arm for single 11 KV over head line conductor complete with 50 mm X 6mm flat iron clamp, bolts, nuts and washers including drilling holes for insulator pins, bolts and nuts etc and painting with primer and finish paint as required.	3.00	set	INR		0.00	INR Zero Only
5	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for two 11 KV over head line conductors complete with 50 mm X 50 mm X 6 mm (angle iron bracket welded to the channel iron and complete with 50 mm X 6 mm M.S. flast iron clamps, bolts and nuts including drilling bolts for insulator pris, bolts, trand washers etc (as per drawing) and painting with primer and finish paint as required.	8.00	set	INR		0.00	INR Zero Only
6	Erection of pole top/ straight two wire/ V shape two wire, angle iron/ channel iron, cross arm on steel tubular/ rail/ PCC pole for 11/22/33 KV as required.	11.00	Set	INR		0.00	INR Zero Only
7	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer et including drilling of holes for insulator pins et (as per drawing) and painting with primer and finished paint as required.	7.00	Set	INR		0.00	INR Zero Only
8	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 2 wire over head line complete with clamps, bolts, nuts and washer ete including drilling of holes for insulator prins ete (as per drawing) and painting with primer and finished paint as reauired.	4.00	Nos.	INR		0.00	INR Zero Only
9	Supplying of two lengths of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metc) double pole cross am for three wire 11kV over head line conductors complete with through boths and nuts for clamping to the poles, 50 mm X 6 mm M 5. flats welded on one side to the channel iron and with bolts and nuts on the other side for tying the cross arms together, including drilling holes for insulator prins fittings, bolts, nuts and washers etc (as per drawing) and painting with primer and finish paint as required.	1.00	Nos.	INR			INR Zero Only INR Zero Only
10	Supplying and erection of gaivanised 10 fron clamps complete with shackle insulator (100 mm X 110 mm), GI bolts, nuts and washers, coach screws ctc. as required. Supplying and erection of 100 mm X 80 mm pin insulator complete with	5.00	Set Set	INR			INR Zero Only
12	G. I. Spindle and nuts etc. as required. Erection of double pole 3 wire cross arm for 11KV/22KV/33 KV over	1.00		INR			INR Zero Only
13	head lines as required. Supplying and erection of 11 KV pin insulator complete with large steel head G.I. pin, nuts, washers etc. as required.	15.00		INR			INR Zero Only
14	Supplying and erection of 11 KV disc insulator for 11 KV over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required.	24.00	Set	INR		0.00	INR Zero Only
15	Erection of cradle guard as required.	96.00	Nos	INR			INR Zero Only
16	Loading, transporting and unloading of poles (truck will be provided by Bhurkunda Project)	3.00	Nos.	INR		0.00	INR Zero Only
	With 3 metre GI pipe having outer pipe dia of 50 mm having 80-200 micron galvanising, inner pipe dia of 25mm having 200-250 micron galvanising, connection terminal dia of 12 mm in nominal soil with 50 KG (two bags) back filling bentonite compound UL listed and confirm to relevant international infalian standard around electrode upto ground level. (Chemical Earthing)	2.00		INR			INR Zero Only
18	Supply and fixing of gang operating switch 400Amps	2.00	set	INR		0.00	INR Zero Only
19	Supply and fixing of aerial bunch cable 35 sqmm 4 core cable	800.00	Mtrs	INR		0.00	INR Zero Only
20	Total impact of GST for the purpose of CTC	1.000	Nos	INR	0.00	0.00	INR Zero Only
Total in Figures				I		0.00	INR Zero Only
Quoted Rate in Words	-	INR Zero Only					