

Item Rate BoQ

Tender Inviting Authority: Project Engineer(E&M), Bhurkunda Colliery, Barka-Saya! Area, CCL.							
Name of the Work / Contract No:	Supply and erection of single phase lighting line at the riverside officers colony under Bhurkunda Colliery.				NIT No. : PE(EnM)/BHK/e Tender/25-26/31 Dated: 04/11/2025		
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)					
ITC Not Available	Works Contract	Bidder's Status (Mandatory)		Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select		0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	12	6	7	8
1	Erection of ACSR conductor of 7/2.11 mm to 7/3.00 mm diameter including binding etc. as required. SPAN X 50 MtrsX 214 Kg/Km= 856 KG	856.00	KG	INR		0.00	INR Zero Only
2	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 2 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required.	80.00	Set	INR		0.00	INR Zero Only
3	Supplying and erection of 100 mm X 80 mm pin insulator complete with G. I. Spindle and nuts etc. as required .	60.00	Set	INR		0.00	INR Zero Only
4	Supplying and erection of 100 mm X 110 mm shackle insulator with G. I. Bolt, nuts and straps etc. as required .	40.00	set	INR		0.00	INR Zero Only
5	Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required. Above 10.00 metre and upto 12.00 metre	5.00	No.	INR		0.00	INR Zero Only
6	Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required. 400 A,50KA,FPMCCB	2.00	No.	INR		0.00	INR Zero Only
7	Total impact of GST for the purpose of CTC	1.000	Nos	INR	0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					