

Item Rate BoQ

Tender Inviting Authority: Project Engineer (E&M), Tetariakhhar OCP

Name of the Work / Extension, Diversion and Dismantling of 480 meters of 200 mm MS/CI delivery pipeline to facilitate operation of three 2000 GPM outsourcing pumps (Total capacity 6000GPM) during pump shifting, until completion of the outsourcing dewatering contract, at the main sump of TTK OCP under
Contract No: Rajhara Area.

.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Laying and erection of G.I pipes 150mm dia	480	Mtr.			0.00	INR Zero Only
2	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 1.5 m, disposed earth to be levelled and neatly dressed. 2.8.1 Ordinary rock .200 Mtr X 1 Mtr X 1 Mtr	200	CUM			0.00	INR Zero Only
3	Dismantling old C.I. pipes including excavation and refilling trenches after taking out the pipes, breaking lead caulked joints, melting of lead and making into blocks, including stacking of pipes at site lead up to 50 meter: 200mm dia MS/CI pipe	480	Mtr.			0.00	INR Zero Only
4	Welding of pipe by gas or electric plant including transportation of plant at site etc. complete.(3.14 x Dia. x total places= 3.14x20cmx220places=13816cm)	13816	CUM			0.00	INR Zero Only
5	Supply & Fixing of CI NR Valve 200mm	3	Nos.			0.00	INR Zero Only
6	Supply & Fixing of CI NR valve 100mm for water tankar filling point	1	Nos.			0.00	INR Zero Only
7	Total impact of GST for the purpose of CTC	1	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					