

Validate

Print

Help

Item Rate BoQ**Tender Inviting Authority: Project Engineer(EnM),SYL-D Project, Barka-Sayal Area, CCL.**

Name of the Work / Contract No:	Erection of LT Over Head line from Shakti Colony to Saunda Check post for newly constructed road lighting.	
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)
ITC Not Available	Works Contract	Bidder's Status (Mandatory)
Name of the Bidder/ Bidding Firm / Company :		Select
		Total GST(in Rs.)
		GST to be Paid By Bidder (in Rs.)
		GST to be Paid By CIL/Subsidiary (in Rs.)
		0.00
		0.00
		0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Erection of metallic pole of following lenth in cement concrete 1:3:6 (1 coarse sand: 6 graded stone aggregate 40mm nominal size) foundation including excavation and refilling etc as required.Above 8.0 meter and upto 10.0 metre. (DP- 8 & SP - 29 Nos)	45	Each		0.00	INR Zero Only
2	Supply & Erection of stay set complete (galvanized) with 19/20 mm dia X 1.8 meters long stay rod, anchor plate of size 45 cm x 45 cm x7.5 mm, thimble, stay clams, turn buckle (20 mm x 60 cm), 7/3.15 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement:3 coarse sand: 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc.	21	Nos		0.00	INR Zero Only
3	Supplying of channel iron 75mm x 40mm x 6mm (7.14 Kg per meter) cross arm for 2 wire over head line complete with clamps, bolts nuts and washer etc including drilling of holes for insulator pins, etc (as per drawing) and painting with primer and finish paint as required. (Additional -6nos for guarding x-arm)	45	Set		0.00	INR Zero Only

4	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required .	45	Set		0.00	INR Zero Only
5	Erection of angle channel iron cross arm on wood RCC/PCC/Steel tubular/rail pole etc. as required.	90	Nos		0.00	INR Zero Only
6	Supplying and erection of 75 mm x 90 mm shackle insulator with GI bolt, nuts and strap etc.	80	Set		0.00	INR Zero Only
7	Supplying and erection of 100 mm x 65 mm Pin insulator with GI bolt and nuts etc as required	145	Set		0.00	INR Zero Only
8	Erection of all aluminium conductor of 7/1.96mm to 7/3.10mm diameter including binding etc. as required.. (1.750KM x 5) x 171/Kg/Km =1496.25 Kg	1496.25	kg		0.00	INR Zero Only
9	Loading, Transporting and unloading of Poles and OH materials from store to working site.	45	per Pole		0.00	INR Zero Only
10	Supplying and fixing of 32 mm dia X 2.00 meters long GI. pipe (medium class) bracket for mounting of fluorescent /HPMV/HPSV street light fitting on pole including bending the pipe to the required shape, 2nos 40 mm X 3 mm flat iron clamp swith nuts, bolts and washer, painting the flatiron with primer and finish paint etc. as required.	40.00	Each		0.00	INR Zero Only
11	Supplying and drawing following sizes of FRLS PVC insulated copper conductor 2 x 2.5 sq. mm (40light x 1.5mtr = 60mtr.)	60	Mtr		0.00	INR Zero Only
12	Fixing of LED street light / Flood light	40	Nos		0.00	INR Zero Only
13	Providing and fixing following capacity TP&N disconnecter fuse switch unit 100A.	1	No		0.00	INR Zero Only
14	Total impact of GST for the purpose of CTC	1.000	No.	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				