

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Project Engineer(EnM),SYL-D Project, Barka-Sayal Area, CCL.

Name of the Work / Contract No:	Repairing and lowering of 2 nos. of submersible pump 10 HP, 440 V,3Ph with related accessories installed at Damodar river side water supply and Kali Mandir water supply of sayal-D project				
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Repairing of 10 hp pump including rewinding, repairing of shaft,impeller,pump body etc along with trial run and testing	2	Each		0.00	INR Zero Only
2	Supplying and laying of submersible flat cable ISI marked 3 core copper wire of suitable size with proper clamping 6.0 sq.mm multi strand	300	Mtr		0.00	INR Zero Only
3	Supply installation, testing and commissioning of approved make DOL starter 10 hp, 3 phase, 50 Hz, 415V, i/c single phase preventer, incoming MCB 32A 4P, 10KA , in outdoor type enclosure, connections, as required as per specifications	2	Nos		0.00	INR Zero Only
4	Supplying and laying of approved make nylon rope 12 mm thick complete with binding for support of pump and motor.	300	Mtr		0.00	INR Zero Only

5	Providing, laying, testing & commissioning of 'C' class heavy duty MS pipe conforming to IS 3589/IS 1239 including Welding, fittings like elbows, tees, flanges, tapers, nuts bolts, gaskets etc. and fixing the pipe on the wall/ceiling with suitable clamp/support frame and painting with two or more coats of synthetic enamel paint of required shade complete as required :50 mm dia	120	Mtr		0.00	INR Zero Only
6	Lowering of submersible pump motor with G.I Pipes per direction of Engineer in charge	2	Each		0.00	INR Zero Only
7	Over head & Contractor profit	1	no		0.00	INR Zero Only
8	Total impact of GST for the purpose of CTC	1.000	No.	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				