

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority:		SO (EnM)					
Name of the Work / Contract No:		Maintenance of 440 V OH line of 42 No. colony, Officer colony and 38 No. colony to provide smooth power supply at Tapin North Open Cast Project, Hazaribagh Area					
		Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE in Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Erection of steel tubular or rail pole strut in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling and secured with holding clamps, bolts, nuts etc. as required.	14	each			0.00	INR Zero Only
2	Erection of all aluminium conductor of 7/1.96 mm to 7/3.10 diameter and above including binding etc as reqd.	2305.14	Kg			0.00	INR Zero Only
3	Supplying and erection of 100 mm X 110 mm shackle insulator with G. I. Bolt, nuts and straps etc. as required .	100	Set			0.00	INR Zero Only
4	Supplying and erection of 100 mm X 80 mm pin insulator complete with G. I. Spindle and nuts etc. as required	330	Set			0.00	INR Zero Only
5	Erection of angle iron/ channel iron cross arm on wood/RCC/PCC/steel tubular/rail pole etc as required.	82	Set			0.00	INR Zero Only
6	Supplying of two lengths of channel iron 100 mm x 50 mm x 6 mm (9.56 kg per metre) double pole cross arm for three wire 33 KV OH line conductors complete with through bolts and nuts for clamps to the poles, 50 mm x 6 mm MS flats welded on one side to the channel iron and with bolts and nuts on the other side for tying the cross arms together, including drilling holes for insulator pins/ fittings, bolts, nuts, washers etc. and painting with primer and finish paint as required.	15	Set			0.00	INR Zero Only
7	Supplying of channel iron 75 mm x 40 mm x 6 mm (7.14 kg per metre) cross arm for four wire OH line complete with clamps, bolts, nuts and washer etc including drilling holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required.	65	Set			0.00	INR Zero Only
8	Supply and Erection of stay set complete (Galvanized) with 19/20 mm dia X1.8 m long stay rod, anchor plate of size 45cmX45cmX7.5mm, thimble, stay clasp, turn buckle (20 mm x 60 cm), 7/4.00mm dia GI stay wire & strain insulator etc in cement concrete 1:3:6 (1 cement:3coarse sand:6 graded stone aggregate 40 mm nominal size) foundation including excavation & refilling and also with 0.6 m long brace of size 50 mm X 50 mm X 6 mm angle iron with 50 mm dia pulley fixed at one end of the brace as required.	15	Each			0.00	INR Zero Only
9	Erection of cradle guard as required.	66	Each			0.00	INR Zero Only
10	Supplying and fixing of 32 mm dia X 2.00 meters long GI pipe (medium class) bracket for mounting of fluorescent/HPMV/HPSV street light fitting on pole including bending the pipe to the required shape, 2 nos 40 mm X 3 mm flat iron clamp with nuts , bolts and washer, painting the flat iron with primer and finish paint etc. as required.	70	Each			0.00	INR Zero Only
11	Dismantling of over head lines comprising of copper/ aluminum over head conductor, G.I wire, cross arms, insulators etc. as required.	4848.24	Kg			0.00	INR Zero Only
12	Dismantling of pole/street light standard/strut embedded in cement concrete foundation etc as required.	25	Each			0.00	INR Zero Only
13	Cradle guard making	66	No.			0.00	INR Zero Only
14	Supply & fixing LT PVC phase separator in 04 wire system	330	No.			0.00	INR Zero Only
15	Pole mugging (Digging - 0.02 Cum/pole, Cement concreting - 0.32 Cum/pole)	35	No.			0.00	INR Zero Only
16	Total impact of GST for the purpose of CTC	1.00	No		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					