

Tender Inviting Authority:	Project Engineer (EnM), TNOCP, Hazaribagh Area					
Name of the Work / Contract No:	Maintenance of earthing arrangement with proper arrangement of raw water at main substation of Tapin North OCP under Hzb Area					
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder In Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required	13	No			0.00	INR Zero Only
2	Providing and fixing 25 mm X 5 mm G.I strip on surface or in recess for connections etc. as required	195	Mtr			0.00	INR Zero Only
3	Providing and laying G.I. tape 32 mm X 6 mm from earth electrode directly in ground as required	195	Mtr			0.00	INR Zero Only
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in Cement mortar 1:6 (1 cement : 6 coarse sand)	15	cum			0.00	INR Zero Only
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	10	cum			0.00	INR Zero Only
6	12 mm cement plaster finished with a floating coat of neat cement of mix 1:4 (1 cement: 4 fine sand)	30	sqm			0.00	INR Zero Only
7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work	150	mtr			0.00	INR Zero Only
8	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work	300	mtr			0.00	INR Zero Only
9	Providing and fixing PTMT bib cock of approved quality and colour 15 mm nominal bore, 90 mm long, weighing not less than 93 gms	30	no			0.00	INR Zero Only
10	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : (25mm nominal bore)	15	no			0.00	INR Zero Only
11	Total impact of GST for the purpose of CTC	1.00	No		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					