Validate Print Help

Validate	Print Help Item Rate BoQ						
Tender Inviting A	uthority: Project Engineer (E&M), Bokaro Colliery						
Name of the Work / Contract No:	Supply, providing and fixing of different rating MCCBs at different locations under Bokaro Colliery, B&K Area ct				NIT No.: CCL/BnK/Bokaro/EnM /25-26/17_1		
	Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract		Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/Bidding Firm / Company			Select	18	0.00	0.00	0.00
	80Q template must not be modified/replaced by the bidder and the same should be uploaded after filling the rele		ns, else the bidder is liable to b				
NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
SI. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	Figures To be	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Supply and providing of 3 pole adjustable Thermal and adjustable magnetic type MCCB of minimum 315A capacity	4	Each			0.00	INR Zero Only
1.02	Supply and providing of 3 pole adjustable Thermal and adjustable magnetic type MCCB of minimum 400A capacity	4	Each			0.00	INR Zero Only
1.03	Fabrication and installation of suitable size panel board suitable for MCCB with proper lock-key arrangement	8	Each			0.00	INR Zero Only
1.04	Fitting and fixing of an adequate rainwater protection shed of suitable size and handling of cable including fresh connection at the pole top	t 8	Each			0.00	INR Zero Only
1.05	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 2 X 35 sq. mm	8	Each			0.00	INR Zero Only
1.06	Supplying of channel iron 75mm X 40mm X 6mm (7.14kg per metre cross arm for 2 wire overhead line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as reauired.	16	Set			0.00	INR Zero Only
1.07	Erection of angle iron/ channel iron cross arm on wood/ RCC/ PCC/ steel tubular/ rail pole etc. as required.	16	Set			0.00	INR Zero Only
1.08	Supply and fixing of radium warning sticker indicating serial number, voltage grade and caution sign on the Switch Fuse Unit	8	Each			0.00	INR Zero Only
1.09	Fitting, fixing charges including other incidental cost @ 10% of Sl. No. 1 & 2	1	Job			0.00	INR Zero Only
2							
	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures	Total impact of GST for the purpose of CTC	1.000	Nos		0.00		INR Zero Only INR Zero Only