

Tender Inviting Authority: Project Engineer (E&M), Bokaro Colliery							
Name of the Work / Contract No:	Repair, maintenance and extension of 220V OH line for providing lighting arrangement in main road from Gandhinagar Substation to CISF VIP gate in respect of Bokaro Colliery				NIT No. : CCL/BnK/Bokaro/EnM /25-26/17_2		
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Supply and providing RCC pole length above 8 meter to 10 meter long of standard strength	15.00	Nos			0.00	INR Zero Only
1.02	Erection of RCC/ PCC pole of following length in brick ballast and ramming the foundation, finishing with 150mm thick cement concrete (1:3:6) layer on top with including excavation and refilling etc as required. Above 8.0 metre and upto 11.0 metre	15.00	Each			0.00	INR Zero Only
1.03	Erection of all aluminium conductor of 7/1.96 mm to 7/3.10 mm diameter including binding etc. as required.	340.00	kg			0.00	INR Zero Only
1.04	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 2 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required .	20.00	set			0.00	INR Zero Only
1.05	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required .	20.00	Set			0.00	INR Zero Only
1.06	Erection of angle iron/ channel iron cross arm on wood/ RCC/ PCC/ steel tubular/ rail pole etc. as required.	40.00	set			0.00	INR Zero Only
1.07	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, turn buckle (20 mm X 60 cm), 7/ 3.15 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	5.00	set			0.00	INR Zero Only
1.08	Transportation of pole from manufacture place to site	15.00	Each			0.00	INR Zero Only
1.09	Supplying and erection of 100 mm X 65 mm pin insulator complete with G. I. Spindle and nuts etc. as required .	26.00	set			0.00	INR Zero Only
1.1	Supplying and erection of 100 mm X 110 mm shackle insulator with G. I. Bolt, nuts and straps etc. as required .	18.00	set			0.00	INR Zero Only
1.11	Supply and providing of 6 SWG GI wire	192.00	Nos			0.00	INR Zero Only
1.12	Erection of GI wire no 8 SWG including binding etc as required	192.00	kg			0.00	INR Zero Only
1.13	Erection of cradle guard as required	150.00	kg			0.00	INR Zero Only
1.14	Dismantling of over head lines comprising of copper/ aluminium over head conductor, G.I. wire, cross arms, insulators etc. as required.	240.00	Each			0.00	INR Zero Only

1.15	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1m above ground level and removal of rubbish upto a distance of 50m outside the periphery of the area cleared	202.00	kg			0.00	INR Zero Only
1.16	Cutting of trunks and branches and disposal of unserviceable material- beyond 30 cm girth upto and including 60 cm girth	50.00	sqm			0.00	INR Zero Only
1.17	Providing and fixing following capacity TP&N disconnector fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required. 63 Amp TP&N	1.00	Each			0.00	INR Zero Only
1.18	Supplying and drawing following sizes of FR PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required. 2x1.5sq.mm	15.00	meter			0.00	INR Zero Only
1.19	Supplying and drawing following sizes of FR PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required. 2x6sq.mm	30.00	meter			0.00	INR Zero Only
1.2	Supply and providing bend pipe for light assembly as per size with clamp and nut bolt	20.00	Nos			0.00	INR Zero Only
1.21	Erection of light fitting on pole	20.00	set			0.00	INR Zero Only
2	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					