

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL

Name of the Work / Contract No:	Repair/ replacement of Pole, Stay Sets, Overhead conductors and other misc. work in LT Overhead GM Office to RCC and MRS under GM Unit, NK Area	NIT No. GM (NK)/EnM/eNIT/2024-25/111; dated 14.11.2025.			
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Dismantling of over head lines comprising of copper / aluminium over head conductor, G.I. wire, cross arms, insulators etc as required	510.00	kg		0.00	INR Zero Only
2	Dismantling of pole / street light standard /strut embedded in cement concrete foundation etc. as required.	3.00	Nos		0.00	INR Zero Only
3	Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc as required. Above 11.00 Metre and upto 13.00 Metre.	6.00	Nos		0.00	INR Zero Only

4	Supplying and erection of stay set complete (galvanized) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, bow tightener, 7/ 3.15 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	7.00	Nos		0.00	INR Zero Only
5	Supplying of channel iron 75 mm x 40 mm x 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required.	8.00	Set		0.00	INR Zero Only
6	Erection of angle iron / channel iron cross arm on wood / RCC / PCC/ Steel Tubular/ rail pole etc. as required.	8.00	Set		0.00	INR Zero Only
7	Supplying and erection of 75 mm x 90 mm shackle insulator with G.I. Bolt, nuts and straps etc. as required.	24.00	Set		0.00	INR Zero Only
8	Supplying and erection of 100 mm x 65 mm pin insulator complete with G.I Spindle and nuts etc as required.	12.00	Set		0.00	INR Zero Only
9	Erection of LV / MV shackle / pin insulator etc. as required.	14.00	Set		0.00	INR Zero Only
10	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above including binding etc. as required.	450.00	kg		0.00	INR Zero Only
11	Supply of 8 / 6 SWG G.I. wire	301.00	kg		0.00	INR Zero Only
12	Erection of cradle Guard as required.	210.00	Nos		0.00	INR Zero Only
13	Cleaning jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	1500.00	sqmm		0.00	INR Zero Only
14	Cleaning, painting of pole with Aluminum paint post applying red oxide zinc chromate primer	6.00	Nos		0.00	INR Zero Only
15	Earthing with G.I. earth plate 600 mm x 600 mm x 6 mm thick including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 mtrs long etc etc. with charcoal and salt as required.	1.00	Nos		0.00	INR Zero Only
16	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only

Total in Figures		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only	